



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

300 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

15-039-20096-00-00  
 VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 07-14-1969  
 JUL 14 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Bob Delaney of Leben Drilling, Incorporated, has this date requested permission to plug the following described well:

Mr. Delaney guarantees payment of the plugging fee.

Operator's full Name: Theo. Gore & Leben Drilling, Inc.

Complete Address: 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name: Coulter Well No. 1

Location: 440' FSL & 440' FEL-SW/4 Sec. 35 Twp. 5 Rge. (E)(W) 28

County: Decatur Total Depth 4180' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Delaney was instructed to plug the well as follows:

311'--8 5/8" Surface casing, cement circulated with 250 Sx.  
Top of Dakota section @ 1490'.

Circulate hole with heavy mud. Pull DP to 1725' and displace 100 Sx.  
cement thru DP. Pull DP to 335' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

A. L. Nichols  
 Conservation Division Agent