



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-039 - 20101 00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Jerb Ogle of Red Tiger Drilling Company, has this date requested permission to plug the following described well:

Mr. Ogle guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Incorporated

Complete Address: 1515 Wichita Plaza Building, Wichita, Kansas

Lease Name: Minnick Well No. 1

Location: 2200' FEL & 440' FSL of Sec. 20 Twp. 5 Rge. (E)(W) 28

County: Decatur Total Depth 4160' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ogle was instructed to plug the well as follows:

290'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1500'.

Circulate hole with heavy mud. Pull DP to 1725' and displace 100 Sx.
cement thru DP. Pull DP to 310' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

RECEIVED
STATE CORPORATION COMMISSION
07-23-1969
JUL 23 1969
CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

W. L. Nichols
Conservation Division Agent