

State of Kansas



15-137-20095-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent) STATE CORPORATION COMMISSION

RECEIVED

JUN 10 1974

CONSERVATION DIVISION Wichita, Kansas

6-10-74

J. Lewis Brock Administrator 500 Insurance Building Wichita, Kansas 67202

Dear Sir:

Mr. Bill Reiter of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Reiter guarantees payment of the plugging fee.

Operator's full Name: F & M Oil Company, Incorporated,

Complete Address: 603 Union Center, Wichita, Kansas.

Lease Name: Schaben Well No. 3

Location: NE-SE-NW Sec. 22 Twp. 5 Rge. (E)(W) 23

County: Norton Total Depth 3590' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Reiter was instructed to plug the well as follows:

168'--8 5/8" Surface casing, cement circulated with 150 Sx. Top of Dakota section @ 750'.

Circulate hole with heavy mud. Pull DP to 975' and displace 110 Cu. Ft. cement thru DP. Pull DP to 185' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

W. L. Nichols Conservation Division Agent JB