



15-137-20090-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 28 1974

CONSERVATION DIVISION
Wichita, Kansas

1-28-74

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Weber of Abercrombie Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Weber guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drilling, Incorporated,

Complete Address: 801 Union Center, Wichita, Kansas.

Lease Name: Hildebrand Well No. 1

Location: CSE-SW-SW Sec. 15 Twp. 5 Rge. (E)(W) 23

County: Norton Total Depth 3600' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Weber was instructed to plug the well as follows:

230'--7 5/8" Surface casing, cement circulated with 140 Sx. (6 3/4" Hole).
Top of Dakota section @ 750'.

Circulate hole with heavy mud. Pull DP to 975' and displace 70 Cu. Ft. cement thru DP. Pull DP to 245' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent