



9

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

FEB 8 1963

CONSERVATION DIVISION
 Wichita, Kansas

RECEIVED
 STATE CORPORATION COMMISSION

FEB 5 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Walter Voth of Knight Casing Pulling Co has this

date requested permission to plug the following described well:

Voth

Mr. Continental Oil Co guarantees payment of the plugging fee.

Operator's full Name: Continental Oil Co

Complete Address: Drawer # 367, Plainville, Kansas

Lease Name: Feely Well No. 3

Location: SE-NE-SW Sec. 2 Twp. 5 Rge. (E) (W) 27

County Decatur Total Depth 3820 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Voth was instructed to plug the well as follows:

Sand well back above top perforations to 3600', Set 4 sx cement
with dump bailer. Pull 5½" casing, set bridge and 20 sx cement
@550'. Fill hole with heavy mud to 315', set plug and 20 Sx.
cement to 258'. (Surface casing cemented @ 268').

This well to be left as a water well for Continental Oil Co.

Very truly yours,

W. L. Nichols
 Conservation Division Agent