

State of Kansas



15-039-20218-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 19 1971
CONSERVATION DIVISION
Wichita, Kansas

10-19-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Dean Ulrich of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Ulrich guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company,

Complete Address: 617 Union Center, Wichita, Kansas.

Lease Name: Tacha Well No. 1

Location: SW-SW-NE Sec. 1 Twp. 5 Rge. (E)(W) 27

County: Decatur Total Depth 3745' Oil Well _____

Gas Well _____ Input Well _____ SWD Well _____ D & A X Lost Hole _____

Mr. Ulrich was instructed to plug the well as follows:

230'--8 5/8" Surface casing, cement circulated with 175 Sx.

Top of Dakota section @ 1000'.

Circulate hole with heavy mud. Pull DP to 1225' and displace 100 Sx.
cement thru DP. Pull DP to 245' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with $\frac{1}{2}$ sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,


J. L. Dickels
Conservation Division Agent