



15-039-20017-00-00

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

JUL 25 1967  
7-25-67

CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Don Favinger of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Favinger guarantees payment of the plugging fee.

Operator's full Name: Raymond Oil Company, Incorporated,

Complete Address: 410 4th National Bank Bldg., Wichita, Kansas.

Lease Name: Feely Well No. 1

Location: NE-SW-NW Sec. 2 Twp. 5 Rge. (E)(W) 27

County Decatur Total Depth 3828' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Favinger was instructed to plug the well as follows:

273' -- 8 5/8" surface pipe, cement circulated with 150 Sx.  
Circulate hole with heavy mud, set plug thru Dakota section  
from 1290' to 1000' with 75 Sx. cement. (Dakota section from  
1100' to 1250') Pull DP. to 275' and displace 20 Sx. cement  
thru DP. Pull DP. set plug @ 40' with 1/2 sack hulls and 10 Sx.  
cement to bottom of cellar.

Very truly yours,

W. L. Nichols  
Conservation Division Agent