



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 4 1968
 CONSERVATION DIVISION
 Wichita, Kansas

9-4-68

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. John Wright of Continental Oil Company, has this

date requested permission to plug the following described well:

Mr. Wright guarantees payment of the plugging fee.

Operator's full Name: Continental Oil Company,

Complete Address: Box #267, Great Bend, Kansas.

Lease Name: C. E. Feely Well No. 2

Location: NW-SE-SW Sec. 2 Twp. 5 Rge. (E)(W) 27

County: Decatur Total Depth 3710 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Wright was instructed to plug the well as follows:

248'--1 3/4" Surface casing, cement circulated. (9" Hole).
3709'--7" OD Production casing cemented to 3000'. Well Plugged back to 3430'.
Top perforations from 3385' to 3390'. Top of Dakota section @ 1125'.

Sand well back to 3370' and set 5 Sx. cement with dump bailer. Pull 7"
casing and squeeze well with 40 sacks gel plus 5 sacks hulls in initial
gel and 175 Sx. cement staged.

Very truly yours,

M. L. Nichols
 Conservation Division Agent