



18-039-00542-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 23 1971
CONSERVATION DIVISION
Wichita, Kansas

12-23-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. John Glenn of Pipe Pullers, Incorporated has this date requested permission to plug the following described well:

Mr. Glenn guarantees payment of the plugging fee.

Operator's full Name: Continental Oil Company,

Complete Address: 3535 NW 58th Street, Oklahoma City, Oklahoma.

Lease Name: Feely LKC Unit Well No. 1

Location: SE-NW-SW Sec. 2 Twp. 5 Rge. (E)(W) 27

County: Decatur Total Depth 3700' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Glenn was instructed to plug the well as follows:

207'--8 5/8" Surface casing, cement circulated with 175 Sx.
3699'--5 1/2" Production casing cemented on bottom with 125 Sx. Well
plugged back to 3666', top of perforations @ 3607'.

Sand well back to 3550' and set 5 Sx. cement with dump bailer. Pull 5 1/2"
casing and squeeze well with 5 sacks hulls 35 sacks gel and 150 Cu. Ft.
cement, staged.

Very truly yours,

W. L. Nichols
Conservation Division Agent