



15-039-00541-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 23 1971  
CONSERVATION DIVISION  
Wichita, Kansas

12-23-71

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. John Glenn of Pipe Pullers, Incorporated has this date requested permission to plug the following described well:

Mr. Glenn guarantees payment of the plugging fee.

Operator's full Name: Continental Oil Company,

Complete Address: 3535 NW 58th Street, Oklahoma City, Oklahoma.

Lease Name: Feely LKC Unit Well No. 4

Location: SE-SW-SW Sec. 2 Twp. 5 Rge. (E)(W) 27

County: Decatur Total Depth 3717' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Glenn was instructed to plug the well as follows:

200'--8 5/8" surface casing, cement circulated with 150 Sx.  
3716'--5 1/2" Production casing cemented on bottom with 150 Sx. Well  
plugged back to 3616', top of perforations @ 3602'.

Sand well back to 3550' and set 5 Sx. cement with dump bailer. Pull 5 1/2"  
casing and squeeze well with 5 sacks hulls, 35 sacks gel and 150 Cu. Ft.  
cement, staged.

Very truly yours,

W. L. Dickel  
Conservation Division Agent