



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

MAR 16 1966
03-16-1966
CONSERVATION DIV. STATE
Wichita Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

15-127-00153-00-00

Dear Sir:

Mr. Ralph Glenn of Glenn & Smith Pipe Pulling has this

date requested permission to plug the following described well:

Francis Weigel
Mr. Glenn guarantees payment of the plugging fee.

Operator's full Name: Francis Weigel,

Complete Address: Gorham, Kansas.

Lease Name: Spiess Well No. 1

Location: NW-NW-SW Sec. 35 Twp. 5 Rge. (E) (W) 25

County Norton Total Depth 4055 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Glenn was instructed to plug the well as follows:

245'--8 5/8" Surface pipe, cement circulated with 150 Sx.

3727'--4 1/2" Production casing cemented with 120 Sx.

No perforations, no plug back.

Push plug to 3700' and set 3 Sx. cement with dump bailer.

Pull 4 1/2" casing and if hole will bail down set bridge and

fill to bottom of cellar with Redi-Mix.

Very truly yours,

R. L. Nichols
Conservation Division Agent