



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-137-20056-00-00

Dear Sir:

Mr. Bob Delaney of Leben Drilling, Incorporated has this date requested permission to plug the following described well:

Mr. Delaney guarantees payment of the plugging fee.

Operator's full Name: Leben et al.

Complete Address: 200 West Douglas, Wichita, Kansas.

Lease Name: Noone Well No. 1

Location: 150' SW of ^{SW} C&E-SE Sec. 34 Twp. 5 Rge. (E)(W) 25

County: Norton Total Depth 3790' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Delaney was instructed to plug the well as follows:

219'--8 5/8" Surface casing, cement circulated.

Top of Dakota section @ 1025'.

Circulate hole with heavy mud. Pull DP to 1250' and displace 100 Sx. cement thru DP. Pull DP to 245' and displace 25 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION

MAY 20 1970
05-20-1970
CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

Conservation Division Agent