

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R. 82-3-117

API NUMBER 15-101-21854-0000

LEASE NAME FULLMER

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Comm. Div.  
office within 30 days.

WELL NUMBER 1

660 Ft. from B Section Line

1,980 Ft. from B Section Line

SEC. 28 TWP. 16 NOR. 28 ~~W~~ (W)

COUNTY Lane

Date Well Completed 12-16-04

Plugging Commenced 12-17-04

Plugging Completed 12-17-04

LEASE OPERATOR CARMEN SCHMITT, INC.

ADDRESS PO BOX 47, GREAT BEND, KS 67530

PHONE (620) 793-5100 OPERATORS LICENSE NO. 6,569

Character of Well D & A

(Oil, Gas, OGA, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-16-04 (date)

by Steve Pfeifer (KCC District Agent's Name)

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom 14,435'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD  
**KCC WICHITA**

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	210'	Cmtd. w/150 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Push plug to 2,212', pump 50 sax cement on plug thru drill pipe; push plug to 1,350' pump 80 sax cement on plug thru drill pipe; push plug to 675', pump 50 sax cement on plug thru drill pipe; push plug to 240', pump 40 sax cement on plug thru drill pipe; push plug to 40', dump 10 sax cement on plug to cellar; dump 15 sax cement down rat hole and 10 sax down mouse hole

Name of Plugging Contractor SHIELDS DRILLING CO. License No. 5184

Address Box 709, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: CARMEN SCHMITT, INC.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas. (Employee of ~~XXXXXXX~~) or (~~XXXXXXXX~~)


above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) Box 709, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 27th day of December, 2004

My Commission Expires:



Glenn Phillips  
Notary Public