


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Decatur County. Sec. 2 Twp. 5S Rge. (E) 27 (W)
Location as "NE/CNW/SW" or footage from lines SE NE SW
Lease Owner Continental Oil Company
Lease Name C. E. Feely Well No. 3
Office Address Drawer 367, Plainville, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 7-24 19 54
Application for plugging filed 1-9 19 63
Application for plugging approved 1-10 19 63
Plugging commenced 1-30 19 63
Plugging completed 2-2 19 63
Reason for abandonment of well or producing formation Producing formation was depleted
If a producing well is abandoned, date of last production 5-26 19 55
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation Lansing-KC Depth to top 3618 Bottom 3800 Total Depth of Well 3820 Feet
Show depth and thickness of all water, oil and gas formations. PB 3670

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-------------------|------------------------|-------------|-------------|--------------|-------------|--------------|
| <u>Lansing-KC</u> | <u>Oil & water</u> | <u>3619</u> | <u>3631</u> | <u>9 5/8</u> | <u>268'</u> | <u>none</u> |
| <u>"</u> | <u>"</u> | <u>3644</u> | <u>3649</u> | <u>5 1/2</u> | <u>3619</u> | <u>1194'</u> |
| <u>"</u> | <u>"</u> | <u>3657</u> | <u>3669</u> | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, sanded hole from 3670 to 3600' and dumped 5 sacks of cement at 3600' with dump bailer. Pulled 5 1/2" casing, bailed hole to 550', set rock bridge to 540', and ran 20 sacks of cement. Mudded hole to 315' and ran 20 sacks cement to 258'. Top of cement was measured at 258' and the well was left open to convert to a fresh water supply well for a waterflood project.

STATE CORPORATION COMMISSION

FEB 13 1963

2-13-63

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Rooks, ss.
L. E. Powell (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Drawer 367, Plainville, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of February, 19 63

My commission expires December 2, 1965

[Signature]
Kenneth J. Querry Notary Public.

ARC-drs
2-11-63
State CRW File

