

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

15-039-00573-00-00

9

Decatur

County. Sec. 2 Twp. 5S Rge. 27 ~~(E)~~ (W)

Location as "NE/CNW%SW%" or footage from lines NW SE SW

Lease Owner Continental Oil Company

Lease Name G. E. Feely Well No. 2

Office Address 3535 NW 58th St., Oklahoma City, Oklahoma 73112

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed June 24, 19 52

Application for plugging filed July 3, 19 68

Application for plugging approved July 9, 19 68


Plugging commenced August 30, 19 68

Plugging completed September 1, 19 68

Reason for abandonment of well or producing formation Lansing-KC depleted.  
Topeka and Howard formations tested dry.

If a producing well is abandoned, date of last production September 6, 19 67

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. W. L. Nichols

Producing formation Lansing-KC Depth to top Bottom Total Depth of Well 3710 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lansing-KC	Oil & Water	3620'	3664'	10-3/4"	248'	None
Topeka	Dry	3452'	3460'	7"	3709'	993'
Howard	Dry	3385'	3390'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back with sand from 3430' to 3370'. Mixed and dumped 5 sx of cement from 3370' to 3345'. Pulled casing. Mixed and pumped in 9 sx of gel and 5 sx of hulls. Mixed and pumped in 130 sx of cement from 1350' to 1025'. Mixed and pumped in 25 sx of gel from 1025' to 275'. Mixed and pumped in 30 sx of cement from 275' to 200'. Mixed and pumped in 6 sx of gel from 200' to 30'. Mixed and pumped in 15 sx. of cement from 30' to base of the cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 27 1968  
CONSERVATION DIVISION  
Wichita, Kansas

9-27-68

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Russ Casing Pulling Inc.

Address Box 1082, Great Bend, Kansas

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.

J. D. Morrow (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *J. D. Morrow*

3535 NW 58th St., Oklahoma City, Okla. 73112

(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of September, 19 68

*Neil P. Martin*

Notary Public.

My commission expires Jan 17, 1968  
State Corp. Comm.  
File

