

L.S.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15-055-00196-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 10/23/59.

Well Operator: Chesapeake Operating, Inc. KCC License #: 32334  
(Owner/Company Name) (Operator's)

Address: P. O. Box 18496 City: Oklahoma City, OK 73154-0496

State: OK Zip Code: 73154-0496 Contact Phone: (405) 848-8000

Lease: Gano Well #: 2-34 Sec. 34 Twp. 21 S. R. 33  East  West

C - NW Spot Location / QQQQ County: Finney

1320 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

1320 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8-5/8" Set at: 300' Cemented with: 225 Sacks

Production Casing Size: 5-1/2" Set at: 2711' Cemented with: 300 Sacks

List (ALL) Perforations and Bridgeplug Sets: 2629-2686'

RECEIVED

JAN 13 2005

Elevation 2903 DF ( G.L. /  K.B.) T.D.: 2712' P.BTD: \_\_\_\_\_ Anhydrite Depth: \_\_\_\_\_

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole  
(Stone Cover Formation)

Proposed Method of Plugging (attach a separate page if additional space is needed): POOH w/tbg & rods, MIRU cementers, pump 400# cotton seed hulls, pump 110' sx cmt, wait 30 min., top off w/mud if necessary, tie onto 5-1/2x8-5/8" annulus, attempt to establish pump in, if able to, pump into annulus mix & pump 50 sx cement, RDMO cementers, weld on cap, clean up location

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

if not explain why? \_\_\_\_\_

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: \_\_\_\_\_

Bud Neff Phone: (620) 277-0803

Address: 4532 W. Jones Avenue City / State: Garden City, KS 67846

Plugging Contractor: Allied Cementing Co., Inc. KCC License #: \_\_\_\_\_  
(Company Name) (Contractor's)

Address: P. O. Box 31, Russell, KS 67665 Phone: ( )

Proposed Date and Hour of Plugging (if known?): \_\_\_\_\_

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 01/10/05 Authorized Operator / Agent: Barbara J. Bale for Jim Reisch  
Jim Reisch (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

**Barbara Bale**

PN# 218408

**From:** Jim Reisch  
**Sent:** Monday, January 10, 2005 10:39 AM  
**To:** Barbara Bale  
**Subject:** Gano #2-34

API 15055-00196

Barbara,  
Here's another one

**Plugging Procedure:**

1. Blow well down. MIRU WOU, POOH with tubing and rods, LD same. MIRU Cementers, dig out bradenhead.
2. Mix and pump 400# cotton seed hulls, mix and pump 110 sx cement. Wait 30 minutes, top off with mud if necessary.
3. Tie onto 5 1/2" x 8 5/8" annulus, attempt to establish pump in, if able to pump into annulus mix and pump 50 sx cement. RDMO cementers.
4. Weld on cap, clean up location.

Thanks

Jim Reisch  
Chesapeake Operating, Inc.  
Bldg #6212, Rm #208  
405-767-4078  
405-879-9544 (fax)

RECEIVED  
JAN 13 2005  
KCC WICHITA

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    Robert E. Krehbiel, Commissioner    Michael C. Moffet, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Chesapeake Operating, Inc.  
PO Box 18496  
6200 N Western Ave.  
Oklahoma City, OK 73154-0496

January 13, 2005

Re: GANO #2-34  
API 15-055-00196-00-00  
NW 34-21S-33W, 1320 FNL 3960 FEL  
FINNEY COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely



David P. Williams  
Production Supervisor

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888