

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
**Type or Print on this Form
Form must be Signed
All blanks must be Filled**

Lease Operator: Ritchie Exploration, Inc.

Address: P. O. Box 783188

Phone: (316) 691-9500 Operator License #: 4767

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 09/07/04 (Date)

by: Pat Stab (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

LKC Depth to Top: 3419' Bottom: 3643' T.D. 3734'

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 051-21561 - 00 - 00

Lease Name: Solomon AP

Well Number: #6

Spot Location (QQQQ): C - N/2 - N/2 - SE

2080' ²¹⁹⁰ Feet from North / South Section Line

4440' ¹⁴⁵⁰ Feet from East / West Section Line

Sec. 31 Twp. 11 S. R. 19 East West

County: Ellis

Date Well Completed: 09/27/78

Plugging Commenced: 09/07/04

Plugging Completed: 09/07/04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
LKC	Oil & Water	3419'	3643'	8 5/8"	167'	-0- RECEIVED
Arbuckle	Water	3730'	3734'	4 1/2"	3741'	-0- JAN 03 2005
						KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforated 4 1/2" csg @ 2025', 1525', 800'. Ran 2" tbg to 2017'. Pumped 50 sx 60/40 pozmix + 10% gel + 300 # Hulls down tbg.
Pulled tbg up to 1025'. Pumped 110 sx 60/40 pozmix + 10% gel + 200 # Hulls down tbg, cement circulated to surface. Pulled tbg out of hole. Loaded 4 1/2" csg with 80sx 60/40 pozmix + 10% gel + 50# Hulls down tbg. Max PSI = 450#. Shutin @ 200#.
Pumped 35sx 60/40 pozmix + 10% gel + 50# Hulls down 8 5/8" csg. Max PSI = 300#. Shutin @ 100#.

Name of Plugging Contractor: Allied Cementing Express Well Service & Supply License #: 99996 6426

Address: P. O. Box 31 Russell, KS 67665 PO Box 19 Victoria KS 67671

Name of Party Responsible for Plugging Fees: Ritchie Exploration, Inc.

State of Kansas County, Ellis, ss.

Ritchie Exploration, Inc.

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 783188 Wichita, KS 67278-3188

SUBSCRIBED and SWORN TO before me this 30 day of December, 20 04

My Commission Expires: _____

Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Signature]

ALLIED CEMENTING CO., INC. 16063

Federal Tax I.D.# [REDACTED]

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
R

DATE <u>9-7-04</u>	SEC.	TWP.	RANGE	CALLED OUT	ON LOCATION	JOB START	JOB FINISH
<u>Solomon AP</u>					<u>9:00am</u>	<u>10:30am</u>	<u>12:45pm</u>
LEASE	WELL # <u>6</u>	LOCATION <u>VOCEMENDO & BUCKEYE RD</u>			COUNTY <u>ELLIS</u>	STATE <u>KS</u>	
OLD OR NEW (Circle one)		<u>2W 3/4" WEL</u>					

CONTRACTOR EXPRESS

TYPE OF JOB PTA

HOLE SIZE _____ T.D. _____

CASING SIZE 4 1/2 DEPTH _____

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

OWNER _____

CEMENT

AMOUNT ORDERED 375 6 3/4 10% GEL

6 HULLS

USED 2.75

COMMON	<u>165</u>	@	<u>7²⁵</u>	<u>1295²⁵</u>
POZMIX	<u>110</u>	@	<u>4¹⁰</u>	<u>451⁰⁰</u>
GEL	<u>22</u>	@	<u>11⁰⁰</u>	<u>242⁰⁰</u>
CHLORIDE		@		
ASC		@		
<u>HULLS</u>	<u>6</u>	@	<u>20⁰⁰</u>	<u>120⁰⁰</u>
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>411</u>	@	<u>1³⁵</u>	<u>554⁰⁵</u>
MILEAGE	<u>8¹/SK/MILE</u>	@		<u>986⁴⁰</u>
TOTAL				<u>3649⁵⁰</u>

EQUIPMENT

PUMP TRUCK CEMENTER MARK

345 HELPER DAVE

BULK TRUCK

378 DRIVER BRUCE

BULK TRUCK

_____ DRIVER _____

REMARKS:

50 SK @ 2000' w/300# HULLS

110 SK @ 1000' w/200# HULLS @ 200'

CEMENT - PULLED TUBING FEED ON TO

4 1/2 MIXED 80 SK w/150# HULLS

MAX 450 SAUT IN 150'

MIXED 35 SK w/150# HULLS DOWN 8 3/4

350 MAX DEPT

SERVICE

DEPTH OF JOB _____

PUMP TRUCK CHARGE _____ 525⁰⁰

EXTRA FOOTAGE _____ @ _____

MILEAGE 48 @ 4⁰⁰ 192⁰⁰

_____ @ _____

_____ @ _____

_____ @ _____

TOTAL 717⁰⁰

CHARGE TO: RETURCE EXPL.

STREET _____

CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

MANIFOLD _____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

TOTAL _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE _____

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

PRINTED NAME _____

RECEIVED
JAN 03 2005
KCC WICHITA



July 28, 2004

RECEIVED
JAN 03 2005
KCC WICHITA

Kansas Corporation Commission
Conservation Division
130 S. Market, Suite 2078
Wichita, Kansas 67202


Re: **Well Plugging Record (CP-4)**
#6 Solomon A "P"
C N/2 N/2 SE
Sec. 31-11S-19W
Ellis County, Kansas

To Whom It May Concern:

Enclosed please find the Well Plugging Record (CP-4) for the above referenced well.

If you have any questions, please feel free to call the undersigned or John Niernberger at 316-691-9500. Thank you for your assistance in this matter.

Sincerely,



Jennifer Foss
Production Assistant

jlf

Enclosures