

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Vincent Oil Corporation  
Address: 125 N Market ST 1075, Wichita, KS 67202-1721  
Phone: (316) 262-3573 Operator License #: 5004  
Type of Well: Oil Docket #: \_\_\_\_\_  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other)* *(If SWD or ENHR)*  
The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: \_\_\_\_\_ (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Lansing-KC Depth to Top: 3290 Bottom: 3364 T.D. 3495  
Arbuckle Depth to Top: 3404 Bottom: 3410 T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 009-22,097 - 00 - 00  
Lease Name: Evers  
Well Number: 1  
Spot Location (QQQQ): \_\_\_\_\_ - NW - NW - NW  
330 Feet from  North /  South Section Line  
4950 Feet from  East /  West Section Line  
Sec. 24 Twp. 19 S. R. 14  East  West  
County: Barton  
Date Well Completed: 10-06-80  
Plugging Commenced: 12-21-04  
Plugging Completed: 12-22-04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
(as above)				8 5/8	841	0
				4 1/2 10.5	3490	2200

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand at 3232', bailed 4 sacks of Portland, ripped 2301', no gain, ripped 2200' worked free, pulled to 1550', pumped 70 sacks, pulled to 900', pumped 40 sacks, pulled to 300', circulated to surface with 75 sacks.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925  
Address: 401 West Main, Lyons, KS 67554

Name of Party Responsible for Plugging Fees: Vincent Oil Corporation  
State of KANSAS County, SEDGWICK, ss.

Richard A. Hiebsch (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) Richard A. Hiebsch

(Address) 125 N. Market, Suite 1075, Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 29th day of December, 2004

Yolanda Eubanks My Commission Expires: \_\_\_\_\_  
Notary Public

RECEIVED  
DEC 30 2004  
KCC WICHITA



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*Ben*