

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

K.A.R. 82-2-117  
RECEIVED

Lease Operator: Murfin Drilling Company, Inc.  
Address: 250 N. Water, Suite 300  
Phone: (316) 267-3241 Operator License #: 30606  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 11/3/04 (Date)  
by: Darrell Dipman w/ KCC in Hays, KS (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
4072-78,4112-16,4153-64 Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
4204-10,4246-52,4291-94 Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

DEC 30 2004

KCC WICHITA

API Number: 15 - 11/6/59 15-153-05161-00 00  
Lease Name: Texaco-Cahoj Unit Cahoj B(48)  
Well Number: #48 #2  
Spot Location (QQQQ): SE - NE - SE  
1650 Feet from  North /  South Section Line  
330 Feet from  East /  West Section Line  
Sec. 18 Twp. 1 S. R. 34  East  West  
County: Rawlins  
Date Well Completed: 11/6/59 12/25/59  
Plugging Commenced: 11/3/04  
Plugging Completed: 11/3/04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	Surface	447	8 5/8	447	0
	Production	Surface	4379	5 1/2	4379	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

TIH w/tbg to 2505'. RU Swift. Pumped 125 sxs SMD cmt & 450# hulls, no circ. Pulled tbg to 1200'. Pumped 80 sxs SMD & 400# hulls & circ cmt to surface. TOH w/tbg. Hooked up to 8 5/8" csg. Pumped 15 sxs SMD & shut in @ 300#. Top off 5 1/2" w/10 sxs & csg stayed full. Job completed @ 3pm. Witnessed & approved by Darrell Dipman w/KCC.

Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606  
Address: 250 N. Water, Suite 300 ; Wichita, KS 67202

Name of Party Responsible for Plugging Fees: Murfin Drilling Company, Inc.  
State of Kansas County, Sedgwick, ss.

Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Robert Orosco  
(Address) 250 N. Water, Suite 300; Wichita, KS 67202



SUBSCRIBED and SWORN TO before me this 29th day of December, 2004  
Kristin Grady My Commission Expires: 2/06/08  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*Blm*

# SWIFT SERVICES, INC.

PO BOX 466

NESS CITY, 67560-0466

# Invoice

DATE	INVOICE #
11/3/2004	7425

BILL TO
Murfin Drilling Co Inc PO Box 661 Colby, KS 67701-0661

**RECEIVED**  
**DEC 30 2004**  
**KCC WICHITA**

TERMS	Well No.	Lease	County	Contractor	Well Type	Well Category	Job Purpose	Operator
Net 30	#48	Texaco Cahoj	Rawlins	Murfin Drilling	Oil	Workover	PTA	Nick

PRICE REFERE...	DESCRIPTION	QTY	UNIT PRICE	AMOUNT
575W	Mileage	120	3.00	360.00T
576W-P	Pump Charge - PTA	1	550.00	550.00T
275	Cotton Seed Hulls	13	25.00	325.00T
330	Swift Multi-Density Standard (MIDCON II)	230	10.25	2,357.50T
581W	Service Charge Cement	350	1.10	385.00T
583W	Drayage	2,052	0.90	1,846.80T
	Subtotal			5,824.30
	Sales Tax		5.30%	308.69

~~PAID FOR~~ *PA 36 Cement*

<b>Thank you for your business.</b>	<b>Total</b>	\$6,132.99
-------------------------------------	--------------	------------



CHARGE TO: *Murfin Drly*

ADDRESS

CITY, STATE, ZIP CODE

TICKET No 7425

PAGE 1 OF 1

SERVICE LOCATIONS 1. <i>Hays, Ks</i> 2. <i>Ness City, Ks</i>	WELL/PROJECT NO. #48	LEASE <i>Texaco Cahaj</i>	COUNTY/PARISH <i>Rawlins</i>	STATE <i>Ks</i>	CITY	DATE <i>11-3-04</i>	OWNER <i>Same</i>
TICKET TYPE <input checked="" type="checkbox"/> SERVICE <input type="checkbox"/> SALES	CONTRACTOR <i>Murfin Drly</i>	RIG NAME/NO.	SHIPPED VIA <i>elt</i>	DELIVERED TO <i>Location</i>	ORDER NO.		
WELL TYPE <i>oil</i>	WELL CATEGORY <i>Play</i>	JOB PURPOSE <i>PTA</i>	WELL PERMIT NO.	WELL LOCATION			
REFERRAL LOCATION	INVOICE INSTRUCTIONS						

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.		UNIT PRICE		AMOUNT
		LOC	ACCT	DF		QTY.	U/M	QTY.	U/M	
575		1			MILEAGE #103	120	mi	3 <sup>00</sup>		360 <sup>00</sup>
576P		1			pump charge - PTA	1	ea	550 <sup>00</sup>		550 <sup>00</sup>
275		1			Cottonseed hulls	13	skt	25 <sup>00</sup>		325 <sup>00</sup>
330		2			SMD cement	230	skt	10 <sup>25</sup>		2357 <sup>50</sup>
581		2			cement Service charge	350	skt	1 <sup>10</sup>		385 <sup>00</sup>
583		2			Drayage	2052	Ton	9 <sup>00</sup>		1846 <sup>80</sup>

RECEIVED  
 DEC 30 2004  
 KOC NICHITA

**LEGAL TERMS:** Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, **PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY** provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS

X *[Signature]*  
 DATE SIGNED *11-3-04* TIME SIGNED *1500*

A.M.  
 P.M.

REMIT PAYMENT TO:

SWIFT SERVICES, INC.  
 P.O. BOX 466  
 NESS CITY, KS 67560  
 785-798-2300

SURVEY	AGREE	UN-DECIDED	DIS-AGREE	PAGE TOTAL	5824 <sup>30</sup>
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?					
WE UNDERSTOOD AND MET YOUR NEEDS?					
OUR SERVICE WAS PERFORMED WITHOUT DELAY?					
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?				TAX	308 <sup>69</sup>
ARE YOU SATISFIED WITH OUR SERVICE? <input type="checkbox"/> YES <input type="checkbox"/> NO				TOTAL	6132 <sup>99</sup>
<input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND					

