

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

RECEIVED

Lease Operator: Murfin Drilling Company, Inc.
Address: 250 N. Water, Suite 300
Phone: (316) 267-3241 Operator License #: 30606

JAN 06 2005

KCC WICHITA

API Number: 15-422152-15-167-03523-00-01
Lease Name: Boxberger, JB
Well Number: #5

Type of Well: SWD Docket #: D-19,497
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

Spot Location (QQQQ): S2 - N2 - SE -
1650 Feet from North / South Section Line
1320 Feet from East / West Section Line
Sec. 10 Twp. 15 S. R. 14 East West

The plugging proposal was approved on: 12/28/04 (Date)
by: Pat Staub w/KCC in Hays, KS (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

County: Russell
Date Well Completed: 4/22/52
Plugging Commenced: 12/28/04
Plugging Completed: 12/28/04

Producing Formation(s): List All (If needed attach another sheet)
3205-09,3255-3395 Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	Surface	205	8 5/8	205	0
	Production	Surface	3205	5 1/2	3205	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RU Allied Cementing mix & pump 75 sx 60/40 10% gel, 500# hull @ 2995', pull tbg to 2200', mix & pump 75 sx, w/300# hulls, pull tbg to 1100' mix & pump 75 sx 200# hulls pull tbg top off 5 1/2" csg & pres to 500#, hook up to 8 5/8" pres to 1000#, used 240 sx 1000# hulls.

P&A 1:15pm. Witnessed by Pat Staub w/KCC in Hays, KS.

Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606

Address: 250 N. Water, Suite 300 ; Wichita, KS 67202

Name of Party Responsible for Plugging Fees: Murfin Drilling Company, Inc.

State of Kansas County, Sedgwick, ss.

Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 250 N. Water, Suite 300; Wichita, KS 67202



SUBSCRIBED and SWORN TO before me this 4th day of January 2005

Kristin Grady My Commission Expires: 2/06/08
Notary Public

[Handwritten mark]

ALLIED CEMENTING CO., INC. 18797

Federal Tax I.D.# ~~XXXXXXXXXX~~

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

WELL FILE

SERVICE POINT: R

DATE <u>12/27/04</u>	SEC.	TWP.	RANGE	CALLED OUT	ON LOCATION <u>10:00 A.M.</u>	JOB START	JOB FINISH <u>1:15 P.M.</u>
LEASE <u>Boxberger</u>		WELL # <u>R 5</u>		LOCATION <u>Russell 5 to Run</u>		COUNTY <u>RS</u>	STATE <u>KS</u>
<input checked="" type="radio"/> OLD OR NEW (Circle one)				<u>1 W 15 1E INTD</u>			

CONTRACTOR <u>Co. Tools</u>	
TYPE OF JOB <u>DHD</u>	
HOLE SIZE	T.D.
CASING SIZE <u>5 1/2"</u>	DEPTH
TUBING SIZE <u>2"</u>	DEPTH
DRILL PIPE	DEPTH
TOOL	DEPTH
PRES. MAX	MINIMUM
MEAS. LINE	SHOE JOINT
CEMENT LEFT IN CSG.	
PERFS.	
DISPLACEMENT	

OWNER	
CEMENT	
AMOUNT ORDERED	<u>350 @ 10/40 1090</u>
	<u>1000 # HULLS</u>
	<u>USED 240 5x 1000 # HULLS</u>

EQUIPMENT	
PUMP TRUCK	CEMENTER <u>Paul</u>
# <u>3100</u>	HELPER <u>Shane</u>
BULK TRUCK	
# <u>378</u>	DRIVER <u>Craig</u>
BULK TRUCK	
#	DRIVER

COMMON	<u>144</u>	@	<u>7.85</u>	<u>1130.40</u>
POZMIX	<u>96</u>	@	<u>4.10</u>	<u>393.60</u>
GEL	<u>57</u>	@	<u>11.00</u>	<u>627.00</u>
CHLORIDE		@		
ASC		@		
HULLS	<u>10</u>	@	<u>20.00</u>	<u>200.00</u>
RECEIVED				
JAN 06 2005				
KCC WICHITA				
HANDLING	<u>385</u>	@	<u>1.35</u>	<u>519.75</u>
MILEAGE	<u>54 1/2</u>	@	<u>1.10</u>	<u>59.70</u>
				TOTAL <u>2623.25</u>

REMARKS:

Truck @ 2900' spot 25 5x w/
500 # HULLS.
2000' SPOT 25 5x w/ 300 #
HULLS. Pulled to 1000' Circ.
Cement w/ 80 5x 1 200 # HULLS.
5 1/2 csg Topped off w/ 10 5x @ 500 #
Annulus - Press to 1000 #

CHARGE TO: Murfin
STREET _____
CITY _____ STATE _____ ZIP _____

SERVICE

DEPTH OF JOB	
PUMP TRUCK CHARGE	<u>525.00</u>
EXTRA FOOTAGE	@
MILEAGE	<u>10</u> @ <u>4.00</u> <u>40.00</u>
MANIFOLD	@
TOTAL <u>565.00</u>	

PLUG & FLOAT EQUIPMENT

	@	
	@	
	@	
	@	
	@	
TOTAL _____		

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE Mark Pohlen

TAX _____
TOTAL CHARGE _____
DISCOUNT _____ IF PAID IN 30 DAYS

PRINTED NAME _____