

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: LARSON OPERATING COMPANY
A DIVISION OF LARSON ENGINEERING, INC.

Address: 562 WEST HIGHWAY 4 OLMITZ, KS 67564-8561

Phone: (620) 653-7368 Operator License #: 3842

Type of Well: oil Docket #: _____
(Oil, Gas, D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)

The plugging proposal was approved on: 8-5-04 (Date)
by: Steve Middleton & Jim Holland (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (if needed attach another sheet)

Cherokee Depth to Top: 4243 Bottom: 4257 T.D. _____

Ft Scott Depth to Top: 4161 Bottom: 4165 T.D. _____

CIBP Depth to Top: 4220 Bottom: _____ T.D. _____

API Number: 15-135-00369-00-00
15 drilled in 1962

Lease Name: Hair

Well Number: 1

Spot Location (QQQQ): C - NE - SE - _____

1980 Feet from North / South Section Line

660 Feet from East / West Section Line

Sec. 29 Twp. 17 S. R. 22 East West

County: Ness

Date Well Completed: 1-17-63

Plugging Commenced: 8-6-04

Plugging Completed: 8-6-04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Cherokee	oil	0	252'	8-5/8"	252'	0'
Ft Scott	oil	0	4387'	4-1/2"	4387'	537'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same, depth placed from (bottom), to (top) for each plug set.

Previously squeezed @ 940' w/ 200 sx. Set CIBP @ 4100' & capped w/ 4 sx cmt. Shot csg @ 775' & squeezed w/ 80 sx. Shot csg @ 654' - could not pull free. Shot csg @ 537' & pulled to 300'. Pumped 50 sx w/ 2 sx hulls. Pulled csg. Topped off 8-5/8" w/ 55 sx - 8-5/8" stayed full. Plugged with 185 sx 60-40 poz w/ 6% gel & 2 sx hulls. Plugging complete @ 5:15 pm, 8-6-04.

Name of Plugging Contractor: Wild West Well Service, Inc. License #: 32592

Address: P.O. Box 433, Ness City, KS 67560-0433

Name of Party Responsible for Plugging Fees: LARSON OPERATING COMPANY, A DIVISION OF LARSON ENGINEERING, INC.

State of KANSAS County, BARTON, ss.

Thomas Larson (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

RECEIVED


JAN 10 2005

(Signature) Thomas Larson President

(Address) 562 WEST HIGHWAY 4 OLMITZ, KS 67564-8561

KCC WICHITA SUBSCRIBED and SWORN TO before me this 6th day of January, 2005.

Carol S. Larson My Commission Expires: _____
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

3