

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: C.H. Todd, Inc.
Address: 100 S. Main Ste. 415 Wichita KS
Phone: (316) 264 7566 Operator License #: 5055
Type of Well: OIL Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 10-4-04 (Date)
by: Jim Holland (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

_____ Depth to Top: _____ Bottom: _____ T.D. _____

_____ Depth to Top: _____ Bottom: _____ T.D. _____

_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-025-20630-00-00
Lease Name: Barby
Well Number: 5-23
Spot Location (QQQQ): NW-SW-NW-
1650 Feet from North / South Section Line
330 Feet from East / West Section Line
Sec. 23 Twp. 34 S. R. 21 East West
County: Clark
Date Well Completed: _____
Plugging Commenced: 10-5-04
Plugging Completed: 10-8-04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				20	85	-
				13 3/8	330	-
				8 5/8	842	-
				5 1/2	5503	2677

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mixed 200 lb hulls & 25 sx cmt to plug bottom perfs from 5409 to 5209, pumped 22 bbls mud spacer, then 200 hulls & 25 cmt from 4280 to 4080. Repumped w/400 lb hulls & 20 sx 4280 to 4105. Pull 5 1/2 to 875. Circ hole w/mud 50 sx 875 to 725, 30 sx 400 to 300, 10 sx 40-0. Cut & capped 8 5/8.

Name of Plugging Contractor: SARGENT AND HORTON PLUGGING, INC. License #: 31151

Address: Rt. 1, Box 49 BA Tyrone, OK 73951-9731

Name of Party Responsible for Plugging Fees: C.H. Todd, Inc.

State of Kansas County, Sedgwick, ss.

David B. Pauly Vice President (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) Carl Byers

(Address) 100, South Main, Suite #415 Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 7th day of January, 2005

Sally R. Byers My Commission Expires: _____
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



RECEIVED
KANSAS CORPORATION COMMISSION
JAN 07 2005

CONSERVATION DIVISION
WICHITA, KS

B