

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Berexco Inc.  
Address: P.O. Box 20380 Wichita, KS 67208  
Phone: (316) 265-3311 Operator License #: 5363  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 11/8/04 (Date)  
by: Ken Jehlik (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
Mississippi Depth to Top: 5671' Bottom: 5676' T.D. 5740'  
Keyes Depth to Top: 5467' Bottom: 5474' T.D. 5740'  
Lower Morrow Depth to Top: 5387' Bottom: 5400' T.D. 5740'

API Number: 15 - 187-20,388 -00-00  
Lease Name: Julius Johns  
Well Number: 1-35  
Spot Location (QQQQ): \_\_\_\_\_ - \_\_\_\_\_ - C - NE  
1320 Feet from  North /  South Section Line  
1320 Feet from  East /  West Section Line  
Sec. 35 Twp. 30 S. R. 41  East  West  
County: Stanton  
Date Well Completed: 5/3/85  
Plugging Commenced: 11/9/04  
Plugging Completed: 11/11/04 *KCC RBAMS afB*

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Mississippi	Water	0	1560'	8 5/8"	1560'	0
Keyes	Oil & Water	0	5739'	5 1/2"	5739'	1840
Lower Morrow	Oil & Water					

RECEIVED  
JAN 10 2005  
KCC WICHITA


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP @5340' & dumped 2 sx cement on top. Cut off 5 1/2" casing @ 1840'. Pulled 5 1/2" casing out & spotted 50 sx cement @1540', 40 sx @ 580', and 10 sx from 40' to surface. Note - there is a CIBP @5630' that was set during original completion.

Name of Plugging Contractor: Eagle Well Services Inc. License #: 7407  
Address: P O Box 1597 Liberal, KS 67905-1597

Name of Party Responsible for Plugging Fees: Berexco Inc.  
State of KANSAS County, SEDGWICK, ss.

Evan C. Mayhew (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Evan C Mayhew  
(Address) P.O. Box 20380 Wichita, KS 67208

SUBSCRIBED and SWORN TO before me this 7th day of January, 20 05  
Diana E Plotner My Commission Expires: Aug 10, 2007  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*[Handwritten mark]*