

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Beren Corporation
Address: P.O. Box 20380 Wichita, KS 67208
Phone: (316) 265-3311 Operator License #: 5364
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)
The plugging proposal was approved on: 12/5/04 (Date)
by: Steve Durrant (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
LSG A Depth to Top: 3920' Bottom: 3923' T.D. 4012'
LSG E Depth to Top: 3998' Bottom: 4012' T.D. 4012'
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-N/A 171-00088-00-00
Lease Name: Chance
Well Number: 1
Spot Location (QQQQ): _____ - SW - SW - SW
330 Feet from North / South Section Line
330 Feet from East / West Section Line
Sec. 19 Twp. 18 S. R. 31 East West
County: Scott
Date Well Completed: 2/51
Plugging Commenced: 12/6/04
Plugging Completed: 12/8/04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
LSG A	Oil & Water	0	287'	8 5/8"	287'	0
LSG E	Oil & Water	0	3998'	5 1/2"	3998'	0

RECEIVED
JAN 10 2005
KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sanded back 5 1/2" casing and dumped 5 sx cement on top of sand. Top of cement @3870'. Perf 4 holes in 5 1/2" casing @1600'. Set cement retainer @1500'. Pumped 50 sx cement below retainer and spotted 10 sx on top of retainer. Spotted 20 sx cement @800'. Filled csg from 300' to surface w/25 sx. Pumped 10 sx down 8 5/8" x 5 1/2" annulus.

Name of Plugging Contractor: Whitetail Crude Inc. License #: 31627
Address: Box 544 Ness City, KS 67560

Name of Party Responsible for Plugging Fees: Beren Corp.
State of KANSAS County, SEDGWICK, ss.

Evan C. Mayhew (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Signature]
(Address) P.O. Box 20380 Wichita, KS 67208

SUBSCRIBED and SWORN TO before me this 7th day of January, 2005
[Signature] My Commission Expires: Aug 10, 2007
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Signature]