

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Decatur

County. Sec. 6 Twp. 5S Rge. XX 26 (W)

Location as "NE/CNW/SW" or footage from lines NW NW SE

Lease Owner R. W. Shields

Lease Name Boyles

Well No. 1

Office Address 308 Rule Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 12-18 1958

Application for plugging filed 12-18 1958

Application for plugging approved 12-18 1958

Plugging commenced 12-18 1958

Plugging completed 12-18 1958

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricus

Producing formation Depth to top Bottom Total Depth of Well 3780 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	255'	8 5/8"	255'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

From 3780' to 601½' - Heavy Rotary Mud
" 601½' to 600' - Wooden Plug
" 600' to 538' - 20 sacks Cement
" 538' to 251½' - Heavy Rotary Mud
" 251½' to 250' - Wooden Plug
" 250' to 188' - 20 sacks Cement
" 188' to 41½' - Heavy Rotary Mud
" 41½' to 40' - Wooden Plug
" 40' to 6' - 10 sacks Cement
" 6' to Surface - Cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor

Address

STATE OF Kansas, COUNTY OF Sedgwick, ss.
William Herbert

(employee of owner) or ~~owner~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

R. R. #3, Box 144B, Wichita 15, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of December, 1958

My commission expires March 4, 1962

Notary Public.

