


15-153-30170-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rawlins County. Sec. 12 Twp. 5S Rge. 31 (E) (W) X
Location as "NE/CNW/SW" or footage from lines NE NE NE
Lease Owner Empire Drilling Company
Lease Name Latimer Well No. 1
Office Address 650 Fourth National Bank Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 3, 1960 19
Application for plugging filed March 3, 1960 19
Application for plugging approved March 3, 1960 19
Plugging commenced March 3, 1960 19
Plugging completed March 3, 1960 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4110 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	136	8 5/8"	123'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug set @ 400' with 20 sacks cement
Plug set @ 120' with 20 sacks cement
Plug set @ 40' with 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION

MAR 14 1960

3-14-60

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Empire Drilling Company
Address 650 Fourth National Bank Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Irwin Kornfeld (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Irwin Kornfeld
650-4th Nat'l. Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of March, 19 60

My commission expires October 21, 1962

Lucille H. Harr
Lucille H. Harr Notary Public.



LOG

RECEIVED
STATE CORPORATION COMMISSION

MAR 14 1960

3-4-60

CONSERVATION DIVISION
Wichita, Kansas

COMPANY: Empire Drilling Company
 CONTRACTOR: Empire Drilling Company
 FARM: Latimer # 1
 LOCATION: NE NE NE of Section 12-5S-31W, Rawlins County, Kansas
 COMMENCED: February 22, 1960
 COMPLETED: March 3, 1960

ELEVATION: 2830 KB
POTENTIAL: D & A

0	to	136	Surface
136	to	2030	Shale-Shells
2030	to	2200	Shale
2200	to	2230	Anhydrite
2230	to	2322	Shale
2322	to	2337	Anhydrite
2337	to	2558	Shale
2558	to	2598	Anhydrite
2598	to	2600	Shale
2600	to	3040	Shale-Shells
3040	to	3535	Lime-Shale
3535	to	3615	Shale-Lime
3615	to	3865	Lime-Shale
3865	to	3911	Lime
3911	to	3921	Lime-Chert
3921	to	4097	Lime
4097	to	4110	Lime-Shale
4110			Rotary Total Depth

SET: 123' 8 5/8" casing with 75 sacks cement.

ELECTRIC LOG TOPS:

Heebner	3822	-992
Toronto	3855	-1025
Lansing	3870	-1040
Base Kansas City	4095	-1265
Schlumberger TD	4107	

CERTIFICATION

I, Irwin Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log on the Latimer # 1, NE NE NE Section 12-5S-31W, Rawlins County, Kansas, as reflected by the files of Empire Drilling Company.

Irwin Kornfeld
Irwin Kornfeld

SUBSCRIBED AND SWORN to before me, a Notary Public within and for Sedgwick County, Kansas, this 11th day of March, 1960.

Lucille H. Harr
Lucille H. Harr

My commission expires October 21, 1962.