

15-153-30164-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Rawlins County. Sec. 5 Twp. 5S Rge. 31 (XX) (W)

Location as "NE/CNW/SW" or footage from lines SE SE SE

Lease Owner Empire Drilling Company

Lease Name Chance "A" Well No. 1

Office Address 650 Fourth National Bank Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 22, 1961 19

Application for plugging filed October 22, 1961 19

Application for plugging approved October 22, 1961 19

Plugging commenced October 22, 1961 19

Plugging completed October 22, 1961 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 4220 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Sand	Clay-Shale	0	193'	8 5/8"	174'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug set at 550' with 20 sacks cement.  
Plug set at 170' with 20 sacks cement.  
Plug set at 10' with 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 31 1961

CONSERVATION DIVISION  
WICHITA

10-31-61

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Empire Drilling Company

Address 650 Fourth National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Dan J. Kornfeld (employer or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dan J. Kornfeld

650 Fourth Nat'l Bk. Bldg., Wichita 2, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 27 day of October, 1961

Lucille H. Harr  
Lucille H. Harr, Notary Public.

My commission expires October 21, 1962



LOG

COMPANY: Empire Drilling Company

CONTRACTOR: Empire Drilling Company

FARM: Chance "A" # 1

LOCATION: SE SE SE of Section 5-5S-31W, Rawlins County, Kansas

COMMENCED: October 11, 1961 ELEVATION: 2958 KB  
 COMPLETED: October 22, 1961 POTENTIAL: D & A

\*\*\*\*\*

0	to	100	Surface Sand-Clay
100	to	193	Surface Clay-Shale
193	to	1420	Shale-Shells
1420	to	1875	Shale-Shells-Pyrite
1875	to	2060	Shale
2060	to	2215	Sandy Lime-Gypsum
2215	to	2375	Shale-Shells
2375	to	2462	Lime-Shale w/Bentonite
2462	to	2480	Gypsum
2480	to	2500	Shale
2500	to	2687	Shale-Pyrite
2687	to	2727	Anhydrite
2727	to	2815	Shale-Shells
2815	to	2945	Shale
2945	to	3485	Lime-Shale
3485	to	3585	Broken Lime
3585	to	3690	Lime
3690	to	3775	Broken Lime
3775	to	3970	Lime
3970	to	4010	Lime-Shale
4010	to	4090	Lime-Chert
4090	to	4220	Lime
4220			Rotary Total Depth

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 OCT 31 1961  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 10-31-61

SET: 174' of 8 5/8" casing with 115 sacks cement.


ELECTRIC LOG TOPS:

Heebner	3925	- 967
Toronto	3958	-1000
Lansing	3973	-1015
Base Kansas City	4205	-1247
Log Total Depth	4220	


\*\*\*\*\*

CERTIFICATION

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log on the Chance "A" # 1, SE SE SE of Section 5-5S-31W, Rawlins County, Kansas, as reflected by the files of Empire Drilling Company.

  
 Dan J. Kornfeld

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 27th day of October, 1961.

  
 Lucille H. Harr, Notary Public

My commission expires October 21, 1962.