

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: WESTPORT OIL AND GAS COMPANY, LP
Address: 5735 PINELAND, SUITE 300, DALLAS, TEXAS 75231
Phone: (214) 692-1800 Operator License #: 33002
Type of Well: OIL Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 12/08/04 (Date)
by: KEN JEHLIK (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
CHEROKEE Depth to Top: 4863' Bottom: 4876' T.D. 5634'
MARMATON Depth to Top: 4722' Bottom: 4725' T.D. 5634'
KANSAS CITY Depth to Top: 4375' Bottom: 4626' T.D. 5634'

API Number: 15-081-20379-00-00
Lease Name: LUCAS, WAYNE
Well Number: 4
Spot Location (QQQQ): _____ - C - NW - NE
4620 Feet from North / South Section Line
1980 Feet from East / West Section Line
Sec. 21 Twp. 28 S. R. 34 East West
County: HASKELL
Date Well Completed: 11/13/85
Plugging Commenced: 12/10/04
Plugging Completed: 12/16/04 *Per 2/3 KCC*

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
CHEROKEE	OIL	0'	1897'	9-5/8"	1897'	0'
MARMATON	OIL	0'	5633'	5-1/2"	5633'	1920'
KANSAS CITY	OIL					

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


MIX & PUMP 300 LBS. HULLS & 25 SXS. CMT. TO PLUG PERFS. @ 4375'; CUT 5-1/2" CSG. @ 1920'; CIRC. WELL W/ PXA MUD; MIX & PUMP A 60 SX. CMT. PLUG @ 1920'-1770'; POOH LAYING DOWN 5-1/2" CSG. TO 750'; MIX & PUMP A 40 SX. CMT. PLUG @ 750'-650'; POOH & LAY DOWN BALANCE OF 5-1/2" CSG.; LOAD HOLE W/ 5 BBLs PXA MUD TO 40'; MIX & SPOT A 12 SX. CMT. PLUG @ 40'-0'; CUT OFF & CAP 9-5/8" CSG. 3' B.G.L.

Name of Plugging Contractor: SARGENT & HORTON PLUGGING, INC. License #: 31151
Address: RR 1, BOX 49BA, TYRONE, OKLAHOMA 73951
Name of Party Responsible for Plugging Fees: Westport Oil and Gas Company, LP
State of Texas County, Dallas, ss.

RECEIVED
JAN 10 2005
KCC WICHITA

Linda Gruver (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Linda Gruver
(Address) 5735 Pineland, Suite 300, Dallas, TX 75231



Subscribed and SWORN TO before me this 6th day of January, 20 05
Janis C Burrow My Commission Expires: 12/09/08
Notary Public