

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: American Warrior Inc.
Address: P.O. Box 399 Garden City Ks. 67846
Phone: (620) 272-4996 Operator License #: 4058
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 1/7/05 (Date)
by: Virgil Clothier (KCC District Agent's Name)
Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☒ No
Producing Formation(s): List All (If needed attach another sheet)
Lansing Depth to Top: 3065' Bottom: 3156' T.D. 3259
Arbuckle Depth to Top: 3248' Bottom: 3256' T.D. 3259

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-053-01803-00-00
Lease Name: Kraft-Prusa
Well Number: 9-1
Spot Location (QQQQ): C - NW - NW - NW
4950 Feet from ☐ North / ☒ South Section Line
4950 Feet from ☒ East / ☐ West Section Line
Sec. 18 Twp. 17 S. R. 10 ☐ East ☒ West
County: Ellsworth
Date Well Completed: 11/1/51
Plugging Commenced: 1/7/05
Plugging Completed: 1/7/05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Lansing	oil	3065'	3156'	85/8	314'	0
Arbuckle	oil	3248'	3256'	51/2	3248'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perf 950', 365'. Run tbg to 950'. Pumped 70sx 60/40 pos. Pulled tbg to 365'. Pumped 65sx 60/40 pos and cir cement to surface. Pulled tbg. Toped casing off with 100sx 60/40 pos, Cir out braden head. Pumped 5 sx down braden head. pressured to 500#

RECEIVED

JAN 11 2005

Name of Plugging Contractor: Swift Services Inc. License #: 32382
Address: P.O. Box 466 Ness City Ks. 67560

Name of Party Responsible for Plugging Fees: American Warrior Inc.


State of Kansas County, Finney, ss.

Jody L. Smith

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) _____

(Address) P.O. Box 399 Garden City Ks. 67846



SUBSCRIBED and SWORN TO before me this 10 day of January

, 20 05

Notary Public

My Commission Expires: 11/4/07