

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Herman L Loeb  
Address: PO Box 524, Lawrenceville IL 62439  
Phone: (812) 853-3813 Operator License #: 3274  
Type of Well: oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 12/28/04 (Date)  
by: Virgil Clothier (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_ Depth to Top: 3066' Bottom: 3071' T.D. 3246'  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-<sup>053</sup>N/A-00043-00-00  
Lease Name: Lorraine Unit (formerly Janzen #1)  
Well Number: 1-1  
Spot Location (QQQQ): \_\_\_\_\_ - SW - SW - NW  
2970 Feet from  North /  South Section Line  
4950 Feet from  East /  West Section Line  
Sec. 12 Twp. 17 S. R. 9  East  West  
County: Ellsworth  
Date Well Completed: \_\_\_\_\_  
Plugging Commenced: 12/28/04  
Plugging Completed: 12/29/04

KCC  
BEM  
1-12-05  
RBDMs  
CP 2/3

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	200'	0
				4 1/2"	3175	0

RECEIVED  
JAN 03 2005  
KCC WICHITA


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

MIRU Klima Well Serv. Lay down rods and tbg. Set CIBP @ 3016', dump 2 sxs portland cement w/ dump bailor. Perforate 1175', 850', and 250'. Run tbg to 1180' and spot 35 sxs, pull tbg to 850' and spot 35 sxs, pull tbg to 250' and circ 4 1/2" full of cement. Lay down tbg, RU swedge to 4 1/2" csg and circ cement thru 8 5/8" w/ 130 sxs, class A cement w/ 2% jel and 3% CC.

Name of Plugging Contractor: Allied Cementing Klima Well Service Inc License #: NA 7023  
Address: PO box 31, Russel KS 67665-0031  
Name of Party Responsible for Plugging Fees: Herman L Loeb  
State of Kansas County, Ellsworth, ss.

KCC  
BEM  
1-12-05  
RBDMs  
CP 2/3

\_\_\_\_\_  
(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me, God.



(Signature) [Handwritten Signature]  
(Address) \_\_\_\_\_

SUBSCRIBED and SWORN TO before me this 30 day of DEC, 2004  
Glenda Morrison My Commission Expires: 11/23/06  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

BEM