

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Herman L Loeb

Address: PO Box 524, Lawrenceville IL 62439

Phone: (812) 853-3813 Operator License #: 3274

Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 12/27/04 (Date)

by: Virgil Clothier (KCC District Agent's Name)

Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☒ No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: 2150' Bottom: 2160' T.D. _____
Depth to Top: 2430' Bottom: 2436' T.D. 2516'
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-053-0004300-00-00

Lease Name: Lorraine

Well Number: 1-2

Spot Location (QQQQ): C - SW - SE - NW

2970 Feet from ☐ North / ☒ South Section Line

2970 Feet from ☒ East / ☐ West Section Line

Sec. 12 Twp. 17 S. R. 9 ☐ East ☒ West

County: Ellsworth

Date Well Completed: _____

Plugging Commenced: 12/27/04

Plugging Completed: 12/28/04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	192'	0
				4 1/2"	3260	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforate 1175', 850', and 250'. Run tbg to 2112' and spot 35 sxs, pull tbg to 1175', spot 35 sxs, pull tbg to 850', spot 35 sxs

Lay down tbg, RU swedge to 4 1/2" and circ cement thru 8 5/8" w 185 sxs. 60/40 4% jel w 3% cc


Name of Plugging Contractor: Allied Cementing Klima Well Service, Inc. License #: NA 7023

Address: PO box 31, Russell KS 67665-0031

Name of Party Responsible for Plugging Fees: Herman L Loeb

State of Kansas County, Ellsworth, ss.

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Ahn Vratel

(Address) _____

SUBSCRIBED and SWORN TO before me this 30 day of DEC, 2004

Glenda Morrison My Commission Expires: 11/30/04
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
JAN 03 2005
KCC WICHITA

pu