

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Berexco Inc.
Address: P.O. Box 20380 Wichita, KS 67208
Phone: (316) 265-3311 Operator License #: 05363
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 12/28/04 (Date)
by: Mike Maier (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Ft. Scott Depth to Top: 4397' Bottom: 4416' T.D. 4551'
Mississippi Depth to Top: 4521' Bottom: 4551' T.D. 4551'
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-135-23,250-00-01
Lease Name: Clyne DWWO
Well Number: 3
Spot Location (QQQQ): _____ - N/2 - NW - SW
2310 Feet from North / South Section Line
4620 Feet from East / West Section Line
Sec. 2 Twp. 16 S. R. 25 East West
County: Ness
Date Well Completed: 7/13/88
Plugging Commenced: 12/29/04
Plugging Completed: 12/29/04

KCC
BEM
1-11-05
KBOms

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface Conductor & Production) | | | | |
|---------------------------|-------------|--|-------|--------|--------|------------|
| Formation | Content | From | To | Size | Put In | Pulled Out |
| Ft. Scott | Oil & Water | 0 | 304' | 8 5/8" | 304' | 0 |
| Mississippi | Oil & Water | 0 | 4551' | 4 1/2" | 4551' | 0 |
| | | | | | | |
| | | | | | | |

RECEIVED
JAN 10 2005
KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Spotted 30 sx cement in 4 1/2" casing @ 3490', 40 sx @ 1349'. Ran tubing to top of cement and tagged. Circulate back to surface with 65 sx cement. Pumped 30 sx cement down 8 5/8" x 4 1/2" annulus.

Name of Plugging Contractor: Professional Pulling Service License #: 32810
Address: P.O. Box 486 Hays, KS 67601

Name of Party Responsible for Plugging Fees: BEREXCO INC.
State of Kansas County, Sedgwick, ss.

Evan C. Mayhew (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God



(Signature) Evan C Mayhew
(Address) P.O. Box 20380 Wichita, KS 67208

SUBSCRIBED and SWORN TO before me this 7th day of January, 2005
Diana E Plotner My Commission Expires: Aug 10, 2007
Notary Public

BEM