

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record
K.A.R. -82-3-117

API NUMBER 15-113-20-728-00-00
LEASE NAME H.D. Unruh
WELL NUMBER 1B

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

660' Ft. from South Line of Section
400' Ft. from West Line of Section

LEASE OPERATOR American Energies Corporation SPOT LOCATION SW/4
ADDRESS 155 N Market, Suite 710 Section 22 Township 19 Range 1W
CITY, STATE, ZIP Wichita, KS 67202 County McPherson
PHONE # 316-263-5785 Date Well Completed 6/5/80
Character of Well Gas/Oil Date Plugging Commenced 12/6/04
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed 12/10/04

The plugging proposal was approved on 12/10/04 (date)
by Mike Wilson (KCC District Agent's Name)

Is ACO-1 Filed? Yes If not, is well log attached? Previously
Producing Formation(s) Mississippi Depth to Top 2911 Bottom T.D. 2964

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface	Water sands	185'	0'	8 5/8"	185'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

12/6 - Moved in, 12/7 - Spotted rig with dozer - run bailer to 2960', put in 110 gal. sand, couldn't pull 5 1/2" slips at 65,000 lbs, used torch to cut off 3" surface pipe, rigged up jacks, worked 5 1/2" - shut down. 12/8 - checked sand at 2855', ran 5 sx cement, rip pipe at 1250', worked 5 1/2" at 160,000 lbs, shut down. 12/9 - worked 5 1/2" - rip pipe at 1004', pulled 24 jts - run 14 jts 2" to 438', 12/10 - cement 35 sx at 438', pull to 250' - cement ro surface, pulled 2".

Name of Plugging Contractor American Energies Corporation
Licence No. 5399
Address 155 N. Market #710 City: Wichita State: Kansas Zip 67202
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: American Energies Corporation (Operator)


STATE OF KANSAS COUNTY OF Sedgwick, ss.

Alan L. DeGood, President (Employee of Operator or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) Alan L. DeGood
(Alan L. DeGood, President, American Energies Corporation)

(Address) 155 North Market, Suite 710 City: Wichita State: Kansas Zip 67202

SUBSCRIBED AND SWORN TO me this 16th day of December, 2004



Melinda S. Wooten
Melinda S. Wooten, Notary Public

My Commission Expires: 3/12/08

Form CP-4
Revised 12-92

RECEIVED
DEC 30 2004
KCC WICHITA

B

EUGENE W. BRYAN SR. 22-19-1W
 R. R. #1 #1-B H. D. UNRUH 660' FSL &
 CANTON, KS. 67428 400' FWL, SW/4
 CONTR TRIANGLE DRILLING CO. CTY McPHERSON

GEOL _____ FIELD RITZ-CANTON EXT (1/8 NE)

E 1587 KB CM 6/5/80 CARD ISSUED 10/16/80 IP F 80 MCFGPD, 2 BO &
 10 BWPD
 API 15-113-20,728 MISS 2920-2945 OA

+	+	+
+	+	+
*	+	+

SMP	TOPS	DEPTH	DATUM
DOUG		2195	- 608
BR LM		2276	- 689
LANS		2343	- 756
FT SC		2885	-1298
CHER		2889	-1302
MISS		2911	-1324
RTD		2964	-1377

8 5/8" 185/100sx; 4 1/2" 2963/40sx

NO DSTS REPORTED

MICT - CO, PF (MISS) 4/2941-2945,
 5/2931-2936, 2/2920-2922 AC 1400 GALS
 KOF 80 MCFGPD & 2 BOPD & 10BWPD

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

RECEIVED
 DEC 30 2004
 KCC WICHITA

American Energies Corp.
 P O Box 516, 136 N Main
 Canton, Ks. 67428
 (620) 628-4424

Doug Ward 620-654-3826
 Cell 620-654-7149

3042

12/6-12/10 2004

COMPANY
 ADDRESS

A&E

ORDERED BY Steve

LEASE AEC-H D Unruh

WELL NO. 1

WORK STARTED 12-6 COMPLETED 12-10-04

PULLED

RUN

JTS.	FT.	DESCRIPTION	EQUIPMENT	JTS.	FT.	DESCRIPTION
			Anchor			
			Mud Anchor			
			Working Barrel			
			Seating Nipple			
24	5 1/2 - 1004, 30'		Tubing			
			Tubing Subs			
			Standing Valve			
			Traveling Valve			
			Pumps			
			Rods			
			Rods			
			Rods			
			Rod Subs			

RECEIVED
 DEC 30 2004
 KCC WICHITA

SERVICES

Unit and Power Tools	Hours	Per Hour	Amount
<u>Franks</u>	32	130/hr.	\$ 4,160.00
One hour road time			\$
Other Charges			\$
			\$
		(Sales Tax 6.3%)	\$ 262.08
		Total	\$ 4,422.08 4422

Remarks: Moved in on 12-6-04 at 8:00AM got stuck shut down
at 10:00AM
Started at 8:00AM on 12-7-04 spotted rig with dozer run
bailer to 2960' put in 110 gal sand couldn't pull 5 1/2 slips at
65,000 lbs went got torch cut off 3" off surface pipe rigged
up jacks worked 5 1/2" shut down at 4:30PM
Started at 8:00AM on 12-8-04 checked sand at 2855
run 5 sacks cement rip pipe at 1250' worked 5 1/2" at
160,000 lbs shut down at 5:00PM started at 8:00AM on 12-9-04
worked 5 1/2" rip pipe at 1004' pulled 24 joints run 14 joints 2" 4
438' shut down at 4:30PM Started at 10:00AM on 12-10-04 cement
35 sacks at 438' pull to 250' cement to surface pull 2" rigged down
moved off at 2:00PM (4)

Douglas Ward

HESSTON CONCRETE INC.

HESSTON CONCRETE, INC.

P.O. BOX 116
9105 N. EMMA CREEK
HESSTON, KS 67062

800-824-0067
620-327-4813

SAND GRAVEL ROCK

- Ready-Mixed Concrete
- Rentals on Ditch Witch®-Air Compressor w/Jackhammer
- Anx® Building Systems Distributor (ICF Forms)
- NUDURA® Building Systems Distributor (ICF Forms)

www.hesstonconcrete.com

CUSTOMER ID	P.O. NUMBER	TRUCK	DRIVER	DATE	TIME LOADED	TIME NEEDED	TICKET #
	H.D. Gacuh	14	Joe Grant	12-10-04			7709925

SOLD TO	DELIVER TO	INSTRUCTIONS
American Energies	Ridge/Hum St 3/4E N side Back in	

QUANTITY THIS LOAD	QUANTITY ORDERED	QUANTITY DELIVERED	PRODUCT CODE	PRODUCT DESCRIPTION	UNIT OF MEASURE	UNIT PRICE	EXTENDED PRICE
		9		KCC Well Drags	Yds	137.00	1233.00
<p>#2 1/2 cut #3/4 sand 160 gallons water → per yard</p>							

RECEIVED
DEC 30 2004
KCC WICHITA

GENERAL TERMS AND CONDITIONS OF DELIVERY

EXTRA WATER ADDED: _____ GALLONS (by request of customer)

Forty-five (45) minutes free unloading time. In consideration of your making delivery back of the street curbline, I (customer) agree to be responsible for all damages done to sidewalks, grounds or otherwise. PERIODIC RATE OF 2% PER MONTH (24% ANNUAL RATE) WILL BE APPLIED TO PAST DUE ACCOUNTS.

I received the above in good condition except as noted.

Received By: Joseph Ward

SUB TOTAL	1233.00
TAX	77.68
TOTAL	1310.68

THANK YOU