

STATE OF KANSAS
STATE CORPORATION COMMISSION
260 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

20108-00-0
00-00

API NUMBER 15-137-20-018

LEASE NAME Nelson C

WELL NUMBER 1

1650 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 12 TWP. 5 RGE. 22W (E) or (W)

COUNTY Norton

Date Well Completed 3-2-76

Plugging Commenced 2-4-92

Plugging Completed 2-4-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR RP Nixon Oper. Inc.

ADDRESS 207 West 12th Hays, KS 67601

PHONE#(913) 628-3834 OPERATORS LICENSE NO. 5252

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-3-92 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? too old If not, Is well log attached? yes

Producing Formation L/KC, Reagan Depth to Top 3245' Bottom 3493 T.D. 3493

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD RECEIVED
2-13-92

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	236'	none
				4 1/2"	3488'	none

STATE CORPORATION COMMISSION
FEB 13 1992
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set
Pulled 4 1/2" bridge plug from hole and perforated Anhydrite @ 1664' and Dakota @ 950'. Ran 2 1/2" tubing to 1660 & mixed 75 sx 65/35 Pozmix, 10% gel w/hulls, and pumped cement down 2 1/2" and circulated. Pulled tubing. Hooked onto 8 5/8" and pumped 35 sx 65/36 Pozmix and shut-in pressure was 500#. This 35 sx was
(If additional description is necessary, use BACK of this form.) (see backside)

Name of Plugging Contractor Jay-Lan Corp. License No. 5128

Address 207 West 12th Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: RP Nixon Oper. Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Dan A. Nixon (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 207 West 12th Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 12th day of February, 19 92

NOTARY PUBLIC - State of Kansas
JOLENE H. KLAUS
My Appt. Exp. 2/5/94

Jolene H. Klaus
Notary Public

