

15-039-00044-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Decatur County. Sec. 20 Twp. 5 S Rge. (E) 26 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NW SW
Lease Owner Herndon Drilling Company
Lease Name Bader #1 Well No. 1
Office Address 423 Mayo Building, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) dry
Date well completed 6-13 1951
Application for plugging filed 6-13 1951
Application for plugging approved 6-13 1951
Plugging commenced 6-13 1951
Plugging completed 6-13 1951
Reason for abandonment of well or producing formation



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19...
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	250'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 240 feet to 40 feet for each plug set.

Went in hole with drill pipe and circulated mud. Laid down drill pipe. Hole filled up 240 feet plug was set at 240' 1/2 sack of hulls on top of plug and 15 sacks of cement. Hole was filled up to 40. Plug was set at 40 feet 1/2 sack of hulls was put on top of plug and 12 sacks of cement

RECEIVED
STATE CORPORATION COMMISSION
JUL 2 1951
CONSERVATION DIVISION
TULSA, OKLAHOMA

11-2-51

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Herndon Drilling Company
Address P.O. Drawer 489, Tulsa, Oklahoma

STATE OF Oklahoma, COUNTY OF Tulsa, ss.
Jack Herndon (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
P.O. Drawer 489, Tulsa, Oklahoma (Address)

SUBSCRIBED AND SWORN to before me this 20th day of June 1951

My commission expires Sept. 19, 1952 [Signature] Notary Public.

23-3273-s 4-50-10M

PLUGGING
FILE SEC 20 T 5 R 26c
BOOK PAGE 88 LINE 19

15-039-00044-00-00

WELL LOG ON BADER #1

Spudding date: 6-1-51
Date casing set: 6-13-51
Date rotary completed: 6-12-51
Date cable completed:

Location:
NW NW SW Sec. 20-5S-26W
Decatur County, Kansas

<u>FROM</u>	<u>TO</u>	<u>FORMATION</u>	<u>REMARKS</u>
0	248	Surface, shale and sand	Ran 12 jts. of 8-5/8" 23# Csg. at 250.27' w/175 Sx. Cement and 200# C. C.
248	1655	Shale and shells	
1655	1865	Shale, shells and lime	
1865	2236	Shale and shells	
2236	2270	Anhydrite	
2270	2635	Shale and shells	
2635	2725	Shale and lime	
2725	3070	Shale and shells	
3070	3290	Shale and lime	
3290	3360	Lime	
3360	3515	Lime and shale	
3515	3982	Lime	
3982	4115	Lime and shale	
4115	4166	Chert and conglomerate	
4166	4170	Chert	
4170	4235	Lime	
4235		TOTAL DEPTH	Set #1 Plug at 240' w/1/2 Sk. of hulls & 15 Sx. cement. Filled hold to 40' and set #2 plug w/1/2 Sk. hulls & 12 Sx. cement.

RECEIVED
COMMISSION
JUL - 2 1951
DIVISION
Kansas
7-2-51

Subscribed and sworn to before me this 20th
day of June, 19 51

I certify the above and foregoing to be a true and exact
copy of the original driller's log on the Bader #1

E. J. Berger
Notary Public

My commission expires:
My commission expires Aug. 28, 1951

HERNDON DRILLING COMPANY

O. J. Moore

PLUGGING
FILE SEC 20 T 5 R 26a
BOOK PAGE 88 LINE 19