

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 185-23074 - 00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date _____

Well Operator: LaVeta Oil & Gas (Owner / Company Name) KCC License #: 32432 (Operator's)

Address: BOX 780 City: Middleberg

State: Va. Zip Code: 20118-0780 Contact Phone: (540) 687 - 3525

Lease: RICHARDSON Well #: 1A Sec. 36 Twp. 22 S. R. 12 East West

- SE - SE - SE Spot Location / QQQQ County: STAFFORD

330 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

330 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8 Set at: 337 Cemented with: U/N Sacks

Production Casing Size: 5 1/2 Set at: 3324 Cemented with: 125 Sacks

List (ALL) Perforations and Bridgeplug Sets: 2772-81

Elevation: 1822 (G.L. / K.B.) T.D.: 3324 P.B.T.D.: 2850 Anhydrite Depth: _____ (Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): AS KCC REQUIRES

Rec 2000' sand 2691 + 55KS
600' 380 40

RECEIVED
DEC 06 2004
KCC WICHITA

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: BEN GRIFFIT

Phone: (540) 687 - 3525

Address: BOX 780 City / State: MIDDLEBERG VA 20118

Plugging Contractor: QUALITY WELL SERVICE (Company Name) KCC License #: 31925 (Contractor's)

Address: 401 W MAIN LYONS KS 67554 Phone: (620) 727 - 3410

Proposed Date and Hour of Plugging (if known?): ASAP 10-15-04 Plugged

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 9/25/04 Authorized Operator / Agent: [Signature] (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Quality Well Service, Inc.

401 West Main
Lyons, KS 67554

Invoice

Date	Invoice #
11/01/2004	602

Bill To
LaVeta Oil & Gas Box 780 Middleberg, VA 20118-0780

P.O. No.	Terms	Lease Name
	net	Richard 1A

Description	Qty	Rate	Amount
Rig Time	18.5	135.00	2,497.50T
Trucking Floor	1	90.00	90.00T
Sand	1	65.00	65.00T
Cement	5	9.00	45.00T
Ripping of Pipe	2	140.00	280.00T
Water Truck	4	60.00	240.00T
Backhoe	2	62.00	124.00T
Phone Calls	1	10.00	10.00T
Clerical Fees	1	10.00	10.00T
Wiping Rubber	1	15.00	15.00T
10-14-04 & 10-15-04 Rigged up. sanded bottom. loaded hole, dug cellar, tore head down, set floor. pulled slips. checked hole, sand at 2691', bailed 5 sacks, ripped 2165', no gain, ripped 2020', worked free, pulled to 600', pumped 45 sacks, pulled to 350', pumped 45 sacks, pulled to 40', pumped 10sacks, laid joint down, tore down, loaded out and filled cellar in.			
Subtotal			\$3,376.50
Sales Tax (6.8%)			\$229.60
Total			\$3,606.10

RECEIVED
DEC 06 2004
KCC WICHITA