

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-039-30102-00-00

RECEIVED
STATE CORPORATION COMMISSION
JAN 15 1970
CONSERVATION DIVISION
Wichita, Kansas
1-15-70

Operator's Full Name Zenith Drilling Corporation, Incorporated.
Complete Address 300 West Douglas, Wichita, Kansas.
Lease Name Noone Well No. 1
Location SW-NE-NW Sec. 27 Twp. 5 Rge. (E) (W) 26
County Decatur Total Depth 3876'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Forbes Casing Pulling Company, Incorporated.
Address Box #221, Great Bend, Kansas. License No. 637
Operation Completed: Hour 1:00 PM Day 10 Month 1 Year 1970

The above well was plugged as follows:

248'--7" OD Surface casing, cement circulated with 135 Sx. (6 1/4" Hole).
3857'--4 1/2" Production casing cemented on bottom with 100 Sx. Top perforations @
3665'. Well Plugged back to 3831'.
Sanded well back to 3600' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
and squeezed well initially with 3 sacks hulls and 6 sacks gel and pressure built to
2250#. Bled well back and squeezed with 70 Sx. cement. Final shut-in pressure--
500#. (Mudding and cementing operations by Allied Cementing).

I hereby certify that the above well was plugged as herein stated.

Signed: *A. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 1/15/70
INV. NO. 1250-W