

KANSAS

*70*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

*15-1939-00090-00-00*

RECEIVED  
STATE CORPORATION COMMISSION

FEB 26 1973

CONSERVATION DIVISION  
Wichita, Kansas

*2-26-73*

Operator's Full Name R. W. Shields,

Complete Address 666 Fourth National Bank Building, Wichita, Kansas.

Lease Name Feely Well No. C-1

Location NE-SE-NW Sec. 6 Twp. 5 Rge. (E) (W) 26

County Decatur Total Depth 3980'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering, Incorporated,

Address Box #698, Great Bend, Kansas. License No. 683

Operation Completed: Hour 12:30 PM Day 21 Month 2 Year 1973

The above well was plugged as follows:

231'--8 5/8" Surface casing, cement circulated with 175 Sx.

3740'--5 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to 3607'. Top of perforations @ 3558'.

Sanded well back to 3500' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing (1025') and squeezed well initially with 5 sacks hulls and 8 sacks gel and followed with 110 Cu. Ft. cement from 1325' to 1000' then 19 sacks gel from 1000' to 250' and followed with 30 Cu. Ft. cement from 250' to 175' then 3 sacks gel from 175' to 40' and finally 10 Cu. Ft. cement from 40' to bottom of cellar. Maximum pump-in pressure-150#. Final shut-in pressure-100#. (Mudding and cementing by Sun Oil Well Cmtg. Inc.).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. L. Nichols*  
Well Plugging Supervisor

DATE 2/28/73  
INV. NO. 7029-W