

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-30167-00-00

RECEIVED
STATE CORPORATION COMMISSION
SEP 5 1968
CONSERVATION DIVISION
Wichita, Kansas
9-5-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Empire Drilling Company,

Complete Address: 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Schmahl Well No. 1

Location NW-NW-NW Sec. 9 Twp. 5 Rge. (E) (W) 31

County Rawlins Total Depth 4211

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Barnes & Sons Pipe Pulling Company,

Address: Box #313, Russell, Kansas. License No. 9

Operation Completed: Hour 3:30PM Day 9 Month 8 Year 1968

The Above well was plugged as follows:

160'--8 5/8" Surface casing, cement circulated with 100 Sx.
4207'--5 1/2" Production casing cemented with 75 Sx.

Sanded well back to 4190' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
and squeezed well with initially 13 sacks gel plus 5 sacks hulls in initial gel and
followed with 100 Sx. cement from 1300' to 975'. then 20 sacks gel from 975' to 175',
followed with 20 Sx. cement from 175' to 115' then 2 sacks gel from 115' to 30' and
finally 10 Sx. cement from 30' to bottom of cellar. Maximum pump-in pressure--500#,
Final shut-in pressure--100#. Checked top of cement 8/19/68 @ 6'. (By Halliburton).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Pichel
Well Plugging Supervisor

DATE 9/4/68
INV. NO. 8409-W