

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-20020-00-00

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 6 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
5-6-68

Operator's Full Name Helberg Oil Company,

Complete Address: Morland, Kansas.

Lease Name G. P. Schmahl Well No. 2

Location NE-SE-NE Sec. 8 Twp. 5 Rge. (E) (W) 31

County Rawlins Total Depth 4180'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Above

Address: \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour 9:30 PM Day 1 Month 5 Year 1968

The Above well was plugged as follows:

200'--8 5/8" Surface pipe, cement circulated with 100 Sx.

Circulated hole with heavy mud. Filled DP to 1825' and displaced 100 Sx. cement thru

DP from 1825' to 1500'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from

215' to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to

bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols  
Well Plugging Supervisor

DATE 5/7/68  
INV. NO. 7691-W