

KANSAS

2
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-20012-00-00

RECEIVED
AUG 17 1967
8-17-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Helberg Oil Company,

Complete Address: Box #32, Morland, Kansas.

Lease Name G. P. Schmahl Well No. 1

Location Appr. NE-NE-NE Sec. 8 Twp. 5 Rge. (E) (W) 31

County Rawlins Total Depth 4175'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 1:00PM Day 12 Month 8 Year 1967

The Above well was plugged as follows:

180'--8 5/8" Surface pipe. cement circulated with 80 Sx.
Dakota section from 1480' to 1600'.

Circulated hole with heavy mud. Pulled DP to 1620' and displaced 80 Sx.
cement thru DP. Pulled DP to 210' and displaced 30 Sx. cement thru DP.
Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. L. Nichols
Well Plugging Supervisor

DATE 8/17/67
INV. NO. 6158-W