



KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-133-20031-00-00

RECEIVED
STATE CORPORATION COMMISSION
AUG 23 1968
CONSERVATION DIVISION
Wichita, Kansas
8-23-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Mull Drilling Company, Incorporated,

Complete Address: 1625 Wichita Plaza Building, Wichita, Kansas.

Lease Name Brown Well No. A-1

Location CNW-NW Sec. 2 Twp. 5 Rge. (E) (W) 31

County Rawlins Total Depth 4285

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Rains & Williamson Oil Company, Incorporated,

Address: 1425 Wichita Plaza Building, Wichita, Ks. License No.

Operation Completed: Hour 7:00 PM Day 21 Month 8 Year 1968

The Above well was plugged as follows:

217'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 1500'.

Circulated hole with heavy mud. Pulled DP to 1725' and displaced 100 Sx. cement thru
DP from 17258 to 1400'. Pulled DP to 245' and displaced 20 Sx. cement thru DP from
245' to 185'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 8/23/68
INV. NO. 8333-U

Signed: N. L. Pichok
Well Plugging Supervisor