

KANSAS

*Y*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-20018-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 29 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
12-29-70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Mull Drilling Company,

Complete Address Box #349, Russell, Kansas.

Lease Name Brown Well No. 1

Location GSW-SE Sec. 2 Twp. 5 Rge. (E) (W) 31

County Rawlins Total Depth 4280'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Forbes Casing Pulling Company, Incorporated,

Address Box #211, Great Bend, Kansas. License No. ~~637~~ 637

Operation Completed: Hour 3:00 PM Day 22 Month 12 Year 1970

The above well was plugged as follows:

204'--8 5/8" Surface casing, cement circulated with 150 Sx.

4093'--4 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to 4055'. Top of cement @ 3950' (Temp. Survey). Top perforations @ 3950'.

Pushed plug to 3900', sanded back to 3850' and set 3 Sx. cement with dump bailer.

Pulled 4 1/2" casing and squeezed well with initially 5 sacks hulls and 15 sacks gel and

followed with 190 Sx. cement from 1650' to 1000' then 20 sacks gel from 1000' to 225'

and followed with 25 Sx. cement from 225' to 150' then 3 sacks gel from 150' to 30'

and finally 10 Sx. cement from 30' to bottom of cellar. Maximum pump-in pressure--

200#. FSIP--100#. (Mudding and Cementing Operations by Globe Oil Well Cementing, Inc.)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *K. L. Nichols*  
Well Plugging Supervisor

DATE 12/31/70

INV. NO. 3132-W