

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-20377-00-00
Spot: NESENW Sec/Twnshp/Rge: 28-11S-33W
3630 feet from S Section Line, 2980 feet from E Section Line
Lease Name: HUBERT P Well #: 1
County: LOGAN Total Vertical Depth: 4720 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: BOX 783188 8100 E 22ND ST. N. #700
WICHITA, KS 67278

PROD Size: 4.5 feet: 4719 200 SX CMT
SURF Size: 8.625 feet: 326 225 SX CMT

\$153⁴⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/23/2004 9:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: PETER FIORINI Company: RITCHIE EXPLORATION, INC. Phone: (785) 623-1506

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 10% gel - 500# hulls.
Plug through casing.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/23/2004 11:45 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface pipe set at 326' w/225 sxs cement.
4 1/2" production casing set at 4719' w/200 sxs cement. PBTD 4650'.
4 1/2" production casing perforated at 1845' - cement circulated to surface using 350 sxs cement.
12-23-2004 - Connected to 4 1/2" production casing - pumped 260 sxs cement with 500# hulls.
Max. P.S.I. 600#. S.I.P. 500#.
Annulus was observed to be full of cement.

Perfs:

Top	Bot	Thru	Comments
4721	4274		
4608	4620		

Remarks: ALLIED CEMENTING COMPANY-TICKET #19688.

Plugged through: CSG

District: 04

PD

Signed

Darrel Dipman

(TECHNICIAN)

INVOICE

Form CP-2/3

DATE

1-7-05

TRK. NO.

2005061040

DEC 27 2004

DATE _____
 OWIE _____

INDEXED
 REPLACEMENT CARD

DONALD C. SLAWSON #1 'P' HUBERT 28-11-33W
 200 DOUGLAS BLDG. 10'W,
 WICHITA, KS. 67202 C NE SE NW
 CONTR SLAWSON DRILLING CTY LOGAN
 GEOL CHARLES SPRADLIN FIELD HUBERT EXT (1/8 W)

ELV 3125 KB SPD 5/16/85 CARD ISSUED 8/22/85 IP P 125 BOPD, NW
 3120 GL DRLG COMP 5/28/85 LKC 4271-4275
 API 15-109-20,377 CHER(JOHN ZN) 4608-4620

+	+	+
+	+	+
+	+	+

LOG	Tops	Depth/Datum	
ANH	2601 + 524	8 5/8 " 326 / 225SX, 4 1/2 " 4719 / 200SX
B/ANH	2626 + 499	DST (1) 4082-4105 (LANS) / 30-60-45-75, REC 1965' MSW, SIP 1181-1173#, FP 180-572 / 604-897#, HP 1904-1888#, BHT 115°
HEEB	4020- 895	DST (2) 4131-4152 (LANS) / 30-60-45-75, REC 300' MSW, SIP 1279-1255#, FP 33-82 / 82-164#, HP 1985-1937#, BHT 115°
TOR	4046- 921	DST (3) 4191-4224 (KC) / 30-30-30-30, REC 30' M, W / OIL SPTS, SIP 1182-1060#, FP 33-33 / 33-41#, HP 2018-1985#, BHT 118°
LANS	4062- 937	DST (4) 4226-4260 (KC) / 30-30-30-30, (1ST OP) WB, DIED / 17", (2ND OP) NB, REC 100' SLI OCMW (3% OIL, 10% M, 87% W), SIP 963-930#, FP 33-49 / 49-66#, HP 2034-2018#, BHT 109°
MUN CR	4198-1073	DST (5) 4257-4280 (KC) / 30-60-45-75, REC 30' SLI OILY GCM (10% G, 6% OIL 84% M), SIP 98-98#, FP 25-33 / 33-41#, HP LTD 4719-1594 RTD 4720-1595
STARK	4284-1159	INFO RELEASED: 2/13/86 - ADDED COMP INFO
BKC	4341-1216	NOTE: INFO RELEASED: 1/30/86 - WAS OIL WELL - TIGHT HOLE (over)
MARM	4376-1251	
PAW	4478-1353	
FT SC	4532-1407	
CHER	4561-1436	
JOHN ZN	4606-1481	
MISS	4667-1542	

COPYRIGHT 1983
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

DONALD C. SLAWSON #1 'P' HUBERT 28-11-33W
 10'W,
 C NE SE NW

2051-2034#, BHT 111°
 DST (6) 4284-4340 (KC) / 30-60-45-75, REC 380' MSW, W / OIL SPTS, SIP 1076-1076#, FP 33-45 / 115-213#, HP 2116-2083#, BHT 119°
 DST (7) 4552-4634 (CHER) / 30-60-45-75, 80' GIP, REC 186' HVLY OILY GCM (26% G, 22% OIL), 155' HOCM (25% OIL, 5% G), 186' HVLY OILY GCM (26% G, 30% OIL), SIP 946-930#, FP 49-164 / 182-262#, HP 2246-2156#
 MICT - CO, PF (JOHN ZN) 4608-4620, W / 2 SPF, SWB DWN, GSO, SDON, PF (JOHN ZN) 4608-4620, AC 1500 GAL (MOD-202), SWB DWN, GSO, PF (LKC) 4271-4275, W / 2 SPF, AC 1250 GAL (28% FE), SWB DWN, SSO, TSTD 60 BO & 6 BWPD, RE-AC (JOHN ZN) 4608-4620, W / 1500 GAL (MOD-202), SWB DWN, GSO, RE-AC (LKC) 4271-4275, W / 1250 GAL (28% FE), SWB DWN, SSO, PLAN TO PMP OFF JOHN ZN, FLUSH PROD & COMMINGLE, SET CIBP AT 4650', RE-AC (JOHN ZN) W / 1250 GAL (28% FE), SWB DWN, GSO, POP, P 125 BOPD, NW, 7/16/85