

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-20483-00-01
Spot: NWNW Sec/Twnshp/Rge: 3-12S-30W
4620 feet from S Section Line, 4620 feet from E Section Line
Lease Name: JENSEN Well #: 1
County: GOVE Total Vertical Depth: 4545 feet

Operator License No.: 5669
Op Name: HELBERG, JERRY M DBA HELBERG OI
Address: PO BOX 32
MORLAND, KS 67650

PROD Size: 4.5 feet: 1810
SURF Size: 8.625 feet: 225

#14771

Well Type: SWD UIC Docket No: D20525.0 Date/Time to Plug: 12/20/2004 1:30 PM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: DON TEETER Company: POE SERVICING INC Phone: (785) 475-3422

Proposed Plugging Method: Ordered 165 sxs 60/40 pozmix - 10% gel - 700# hulls.
Plug through casing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/29/2004 2:40 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 225' w/160 sxs cement.
4 1/2" production casing set at 1810'.
TD 4545'. PBTd 1810'.
Connected to 4 1/2" production casing - pumped 100 sxs cement with 650# hulls.
Max. P.S.I. 1000#. S.I.P. 500#.
Connected to 8 5/8" surface casing - pumped 15 sxs cement with 50# hulls.
Max. P.S.I. 300#. S.I.P. 0#.

Perfs:

Top	Bot	Thru	Comments
1765	1795		
1718	1748		
1690	1710		

RECEIVED
JAN 11 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #19877.

Plugged through: CSG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

INVOICED

DATE 1-11-05
INV. NO. 2005061051

Form CP-2/3

JAN 04 2005

DATE
TIME

INDEXED

HELBERG OIL COMPANY
 BOX 32 MORLAND, KS 67650 #1 JENSEN "OWWO" 3-12-30W
 C NW NW
 CONTR COMPANY TOOLS CTY GOVE
 GEOL FIELD CARL EXT(1/8 E)

E 2878 KB CM 9/1/63 CARD ISSUED 4/9/81 IP SWDW
 CED HILL 1690-1795
 OA

▲	+	+
+	+	+
+	+	+

API 15-063-20,483-A

LOG	TOPS	DEPTH	DATUM
HEEB		3865	- 987
TOR		3886	-1008
LANS		3903	-1025
B KC		4192	-1314
PAW		4318	-1440
FT SC		4386	-1508
CHER		4418	-1540
MISS		4472	-1594
LTD		4545	-1667

OLD INFO: OPERATOR WAS PICKRELL DRLG.,
 #1 JENSEN, SPD 9/1/63, SET 8" 225/
 160SX, COMPLETED AS D&A(MISS) 9/19/63,
 DST 4491-4500/30", 10' M, BHP 1160-
 847#/30", FP 23-31#:
 DST 4500-10/90", 50' OCM, BHP 1191-
 1100#/30" FP 36-94#:
 NEW INFO: RE-ENTERED 1/2/81, WSH DWN TO
 1500, OUT OF HOLE, DRILLED NEW HOLE TO
 1810 TD, SET 4" 1810, MICT - CO, PF
 (CED HILL) 90/1765-95, 90/1718-48,
 60/1690-1710, SWB DWN, NAT, SWDW -
 INJECTION RATE SATISFACTORY

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS