

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-20497-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 3-12S-30W
4620 feet from S Section Line, 4620 feet from E Section Line
Lease Name: JENSEN Well #: 2
County: GOVE Total Vertical Depth: 4540 feet

Operator License No.: 5669
Op Name: HELBERG, JERRY M DBA HELBERG OI
Address: PO BOX 32
MORLAND, KS 67650

PROD Size: 4.5 feet: 4540
SURF Size: 8.625 feet: 231

\$147⁵⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/29/2004 10:00 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: DON TEETER Company: POE SERVICING INC Phone: (785) 475-3422

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 10% gel - 500# hulls.
Plug through tubing.

Plugging Proposal Received By: HERB DEINES
Date/Time Plugging Completed: 12/29/2004 1:45 PM

Witness Type: COMPLETE (100%)
KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 231' w/150 sxs.
4 1/2" production casing set at 4540' w/175 sxs.
TD 4540'. PBTD 4539'.
4 1/2" production casing parted at 1952'.
The operator made several unsuccessful attempts to repair the well.
Ran tubing to 1900' - pumped 90 sxs cement with 400# hulls.
Cement circulated to surface. Pulled tubing to surface.
Connected to 4 1/2" production casing - pumped 15 sxs cement with 100# hulls.
Max. P.S.I. 1500#. S.I.P. 1500#.
Connected to 8 5/8" surface casing - pumped 15 sxs cement.
Max. P.S.I. 100#. S.I.P. 0#.

Perfs:

Top	Bot	Thru	Comments
4496	4502		

RECEIVED
JAN 11 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #19876.

Plugged through: TBG

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

INVOICED

DATE 1-11-05

INV. NO. 2005061051

Form CP-2/3

JAN 04 2005

