

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-20010-00-00  
Spot: SESWSE Sec/Twnshp/Rge: 15-1S-18W  
330 feet from S Section Line, 1550 feet from E Section Line  
Lease Name: C W O'NEILL Well #: 1  
County: PHILLIPS Total Vertical Depth: 3575 feet

Operator License No.: 31569  
Op Name: BACH, JASON DBA BACH OIL PRODUC  
Address: RR 1, BOX 28  
PHILLIPSBURG, KS 67661

PROD Size: 4.5 feet: 3577 50 SX CMT  
SURF Size: 8.625 feet: 206 150 SX CMT

# 11/6 19

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/12/2004 12:40 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: JASON BACH Company: BACH, JASON DBA BACH OIL PRO Phone: (785) 476-5254

Proposed Plugging Method: Ordered out 175 sxs Swift Multi-Density cement - 500# hulls - 15 sxs gel.  
WL 3410'. FL 750'.

Plugging Proposal Received By: DENNIS HAMEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/12/2004 3:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Tied onto 8 5/8" and pumped 35 sxs cement.  
Max. P.S.I. 300#. S.I.P. 50#.  
Swaged onto 4 1/2" - pumped 16 sxs cement with 150# hulls, followed with 15 sxs gel.  
Topped with 65 sxs cement and 225# hulls.  
Max. P.S.I. 800#. S.I.P. 325#.

Perfs:

Top	Bot	Thru	Comments
3769	3778		
3411	3418		
3388	3394		

RECEIVED  
JAN 11 2005  
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

Signed Jay Pfeifer  
(TECHNICIAN)

INVOICED

DATE 1-11-05  
INV. NO. 2005061049

Form CP-2/3

Rec'd  
11-16-04

