

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-20037-00-00  
Spot: NENE Sec/Twnshp/Rge: 16-1S-18W  
4620 feet from S Section Line, 660 feet from E Section Line  
Lease Name: O'NEILL A Well #: 1  
County: PHILLIPS Total Vertical Depth: 3585 feet

Operator License No.: 31569  
Op Name: BACH, JASON DBA BACH OIL PRODUC  
Address: RR 1, BOX 28  
PHILLIPSBURG, KS 67661

PROD Size: 4.5 feet: 3450 200 SX CMT  
SURF Size: 8.625 feet: 220 160 SX CMT

# 116<sup>51</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/12/2004 11:20 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: JASON BACH Company: BACH, JASON DBA BACH OIL PRO Phone: (785) 476-5254

Proposed Plugging Method: Ordered out 175 sxs Swift Multi-Density cement - 500# hulls - 13 sxs gel.  
WL 3400'. FL 450'.

Plugging Proposal Received By: DENNIS HAMEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/12/2004 12:40 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Tied onto 8 5/8" and pumped 35 sxs cement with 75# hulls.  
Max. P.S.I. 300#. S.I.P. 150#.  
Swaged onto 4 1/2" - mixed and pumped 16 sxs cement with 150# hulls,  
followed with 13 sxs gel.  
Topped with 70 sxs cement with 225# hulls.  
Max. P.S.I. 800#. S.I.P. 450#.

Perfs:

Top	Bot	Thru	Comments
3425	3428		
3420	3422		
3380	3386		

RECEIVED  
JAN 11 2005  
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

Signed Jay Pfeifer (TECHNICIAN)

INVOICE

DATE 1-11-05  
INV. NO. 2005061049

Rec'd.  
11-15-2004

WADICE

16-1-18W  
C NE NE

LELAND R. BAIRD  
LOGAN, KS.  
Contr. RED TIGER DRLG.  
Geol. STEVE POWELL

OWLE #1 O'NEILL A  
PHILLIPS  
HUFFLUTTER EXT

E.2141 KB Cm.4/26/68 Cp. 7/3/68 IP P. 40 BOPD N/W  
LANS 3380-3428

SMP Tops	Depth	Datum
ANH	1735	+ 406
HOW	3086	- 945
TOP	3209	-1068
HEEB	3299	-1158
TOR	3330	-1189
LANS	3347	-1206
BKC	3566	-1425

Csg. 8-5/8" 220; 4 1/2" 3450/200SX  
 DST 3366-90/1', 15' OIL, 20' HOCM,  
 60' OCM, FBHP 1102#/30", FP  
 56-80#  
 DST 3390-3414/1', 20' OSM, FBHP  
 80#/30", FP 40-40#  
 DST 3414-34/1', 10' OSM, FBHP 240#  
 30", FP 32-40#  
 DST 3487-3505/1', 100' M, FBHP  
 224#/30", FP 64-88#  
 PF 3420-22 & 3425-28; MA 250  
 A 3000; REC LD, SWB 2 BWPH, BP  
 3400; PF 3380-86; A 3000, REC LD  
 SWB 3 BOPH N/W 2 HRS, CO PLUG,  
 SWB 10 BOPH N/W 3 HRS, POP

RTD 3587 L-1446  
INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS