

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-20107-00-00
Spot: N2NWSW Sec/Twnshp/Rge: 10-1S-18W
2310 feet from S Section Line, 4620 feet from E Section Line
Lease Name: WITTFOTH Well #: 2
County: PHILLIPS Total Vertical Depth: 3570 feet

Operator License No.: 31569
Op Name: BACH, JASON DBA BACH OIL PRODUC
Address: RR 1, BOX 28
PHILLIPSBURG, KS 67661

PROD Size: 4.5 feet: 3569 150 SX CMT
SURF Size: 8.625 feet: 219 200 SX CMT

03
116

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/12/2004 9:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JASON BACH Company: BACH, JASON DBA BACH OIL PRO Phone: (785) 476-5254

Proposed Plugging Method: Ordered out 175 sxs Swift Multi-Density cement - 500# hulls - 12 sxs gel. WL 3450'. FL 450'.

Plugging Proposal Received By: DENNIS HAMEL WitnessType: NONE
Date/Time Plugging Completed: 11/12/2004 11:20 AM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Tied onto 8 5/8" and pumped 16 sxs cement with 75# hulls.
Max. P.S.I. 250#. S.I.P. 150#.
Swaged onto 4 1/2" - mixed and pumped 16 sxs cement with 150# hulls,
followed with 12 sxs gel.
Topped with 65 sxs cement and 225# hulls.
Max. P.S.I. 600#. S.I.P. 250#.

Perfs:

Top	Bot	Thru	Comments
3500	3514		
3470	3494		
3396	3420		
3351	3375		

RECEIVED
JAN 11 2005
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

Signed Dennis Z. Hamel
(TECHNICIAN)

INVOICED
DATE 1-11-05
INV. NO. 2005061049

Rec'd
11-15-04.


CORRECTED CARD

10-1-18W
C N/2 NW SW

LELAND R. BAIRD
LOGAN, KANSAS
CONTR. B & B DRILLING, INC. CITY PHILLIPS

GEOL. STEVE POWELL FIELD HUFFSTUTTER

E 2110 KB CM 9/27/70 CARD ISSUED 10/29/70 P 30 BOPD N/W
LKC 3385 1/2 -86



API 15-147-20,107

LOG	TOPS	DEPTH	DATUM	
* ANHY	1714	+ 396		8 5/8" 219/145sx; 4 1/2" 3569/125sx
B ANHY	1730	+ 380		DST(1) 3351-75/1', 25' SOCM(GSFO), FBHP 768#/60", FP 40-48#
TQP	3094	- 984		DST(2) 3375-96/1', 10' SOCM(SFO), FBHP 856#/60", FP 32-32#
HEFB	3284	-1174		DST(3) 3396-3420/1', 5' M, FBHP 56#/60", FP 32-32#
TQR	3314	-1204		DST(4) 3470-94/1', 1' M, FBHP 32#/60" FP 32-32#
LKC	3332	-1222		DST(5) 3490-3514/1', 5' M, ALL PRESS 0#
BKC	3552	-1442		
LTD	3571	-1461		
* SAMPLE TOPS				

CORRECTED CARD: 9/16/71
 WAS: C N/2 NW
 IS: C N/2 NW SW
 MICT, PF 2/3386, 2/3385 1/2 A750 (28%) SWB
 LD SWB 2.82BOPH A2500 (15%) SWB LD & SWB
 3.50BOPH, PF 2/3364 1/2 -2/3365 1/2 BP 3375
 CHANNELED PULL PLUG AC W/3250-INJ 10BPM
 SWB LD & SWB 12BOPH/8HRS OB

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS