

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-00787-00-00
Spot: NENWNE Sec/Twnshp/Rge: 6-2S-18W
4950 feet from S Section Line, 1650 feet from E Section Line
Lease Name: HUFFSTUTTER A Well #: 7
County: PHILLIPS Total Vertical Depth: 3507 feet

Operator License No.: 31569 PROD Size: 5.5 feet: 3504 150 SX CMT
Op Name: BACH, JASON DBA BACH OIL PRODUC SURF Size: 8.625 feet: 182 125 SX CMT
Address: RR 1, BOX 28
PHILLIPSBURG, KS 67661

113⁹⁸

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/10/2004 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JASON BACH Company: BACH, JASON DBA BACH OIL PRO Phone: (785) 476-5254

Proposed Plugging Method: Ordered 175 sxs Swift Multi-Density cement - 500# hulls - 15 sxs gel.
WLM 3490'. Recovered tubing fish prior to plugging.
TOF 700'+. Casing squeeze at 1120'.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/10/2004 11:00 AM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Rigged up cementers to 5 1/2" casing - squeezed 16 sxs SMD with 200# hulls, followed with 15 sxs gel, followed with 80 sxs SMD with 200# hulls.
Max. P.S.I. 300#. S.I.P. 100#.
Rigged up cementers to 8 5/8" S.P. - squeezed 16 sxs SMD with 100# hulls mixed in cement.
Max. P.S.I. 200#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3499	3505		
3486	3489		
3473	3476		
3461	3466		
3440	3443		
3408	3411		

RECEIVED
JAN 11 2005
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed Dennis L. Hamel
(TECHNICIAN)

INVOICED

DATE 1-11-05

INV. NO. 2005061049

Form CP-2/3

NOV 24 2004

ADVISED

STABLEFORD & B & R #7 HUFFSTUTTER A 6-2-18W
 NE NW NE

Contr. B & R DRILLING, INC. PHILLIPS County

E 2238 Comm. Comp. 12-1-50 IP 140 BOPD
 PHY POT

Tops	Depth	Datum
HEEB	3361	-1123
LANS	3393	-1155
T.D.	3507	-1269

Casing
 8" 182 PERF 3499-3505
 5" 3504 ACID 1000: 3/4 BOPH
 PB 3486: PERF 3461-
 66: ACID 5000:
 SWB 5 1/2 BOPH

HUFFSTUTTER POOL

+	+	+	+
+	+	+	+

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS